

To: 1 020102  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-12-87  
API NUMBER 15-175-20,975-0000

SE SE SW, SEC. 32, T 31 S, R 31 W/E  
330 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5263

2970 feet from E section line  
Lease Name Rosson Farms Well # 1-32

Operator: Midwestern Exploration Co.  
Name & Address 111 East 11th Street, Box 1884  
Liberal, KS 67901

County Seward 195.00

Well Total Depth 6000 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1650

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sage Drilling Company License Number 5421

Address 202 So. St. Francis, Wichita, KS 67202

Company to plug at: Hour: 8:15 p.m. Day: 11 Month: 10 Year: 19 87

Plugging proposal received from Virgil Shawn

(company name) Sage Drilling Company (phone) 316-263-6139

work: to fill hole with heavy mud and spot cement through drill pipe Elevation 2809'

1st plug at 1700' with 50 sx cement, 2nd plug at 650' with 35 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 10 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:45 p.m. Day: 12 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1700' with 50 sx cement,

2nd plug at 650' with 35 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 10 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
(check) (plus note) observe this plugging.

DATE 10-20-87

INV. NO. 18577  
10-12

Signed Glenn R. Barlow  
(TECHNICIAN)

# NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... OCTOBER 4, 1987.....  
month day year

API Number 15- 175-20,975-0000

OPERATOR: License # 5263  
Name... MIDWESTERN EXPLORATION CO.  
Address... 111 E. 11th St., Box 1884  
City/State/Zip... LIBERAL, KS 67901  
Contact Person... JACK REESE  
Phone... (316) 624-3534

SE SE SW Sec. 32 Twp. 31 S, Rg. 31 East X West  
..... 330 ..... Ft. from South Line of Section  
..... 2970 ..... Ft. from East Line of Section

CONTRACTOR: License # 5421  
Name... SAGE DRILLING CO.  
City/State... WICHITA, KS 67202

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line ..... 330 ..... feet  
County..... SEWARD

Well Drilled For: Well Class: Type Equipment:  
X Oil \_\_\_\_\_ Storage \_\_\_\_\_ Infield X Mud Rotary  
\_\_\_\_\_ Gas \_\_\_\_\_ Inj X Pool Ext. \_\_\_\_\_ Air Rotary  
\_\_\_\_\_ OWWO \_\_\_\_\_ Expl \_\_\_\_\_ Wildcat \_\_\_\_\_ Cable

Lease Name: ROSSON FARMS Well # 1-32  
Ground surface elevation 912.820 feet MSL

Domestic well within 330 feet: \_\_\_\_\_ yes X no  
Municipal well within one mile: \_\_\_\_\_ yes X no

If OWWO: old well info as follows:  
Operator .....  
Well Name .....  
Comp Date ..... Old Total Depth.....

Depth to bottom of fresh water..... 600 .....  
Depth to bottom of usable water ..... 500 .....

Surface pipe by Alternate: 1 X 2  
Surface pipe planned to be set ..... 1650 .....

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.  
Date 9/29/87 Signature of Operator or Agent [Signature] Title... AS AGENT

Conductor pipe required .....  
Projected Total Depth ..... 6000 ..... feet

Formation... MISSISSIPPIAN

For KCC Use:  
Conductor Pipe Required ..... feet; Minimum Surface Pipe Required ..... 550 feet per Alt. 1 X  
This Authorization Expires 3-29-88 Approved By [Signature] 9-29-87

EFFECTIVE DATE: 10-3-87

10-1-87 -  
Set - 1650 ~

SE SE SW Sec. 32 Twp. 31 S, Rg. 31 East X West

## PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. <u>1600-1300</u>	or formation with <u>50</u>	feet of <u>60/40</u> poz
2nd plug @ ft. deep. <u>600</u>	or formation with <u>25</u>	feet of
3rd plug @ ft. deep. <u>40</u>	or formation with <u>10</u>	feet of
4th plug @ ft. deep	or formation with	feet of
5th plug @ ft. deep	or formation with	feet of
(2) Rathole to surface minus 5 feet <u>5</u>		(b) Mousehole to surface minus 5 feet <u>5</u>

Virgil Shuman  
Candy  
 PUSHER \_\_\_\_\_  
 TD 6000 FORMATION \_\_\_\_\_  
 SURFACE PIPE 8 7/8 @ 1650  
 ANHYDRITE \_\_\_\_\_ ELEVATION 2829  
 STARTING TIME & DATE OCT 11 - 8:15 P.M.  
 COMPLETION TIME & DATE 6 OCT 28 2:45 P.M.  
 1st PLUG @ 1700 FT. W/ 50 SX  
 2nd PLUG @ 650 FT. W/ 35 SX  
 3rd PLUG @ 40 FT. W/ 10 SX  
 4th PLUG @ \_\_\_\_\_ FT. W/ \_\_\_\_\_ SX  
 RAT HOLE CIRCULATED W/ 10 SX  
 MOUSE HOLE CIRCULATED W/ 10 SX  
 WATER WELL PLUGGED W/ \_\_\_\_\_ SX  
 CEMENT COMPANY HILLBURN  
 TECHNICIAN \_\_\_\_\_

SRW  
 RECEIVED  
 STATE CORPORATION COMMISSION  
10  
 OCT 16 1987  
 CONSERVATION DIVISION  
 Wichita, Kansas