

1060430

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 S/2, SEC. 34, T 31 S, R 31 W/X
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,473-0000 *RV*

660 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5028

Lease Name Reiss Well # 1-34

Operator: Imperial Oil Company

County Seward

Name & Address 720 4th Financial Center

Well Total Depth 6000 ^{195.00} feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1612

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 12 Month: December Year: 19 84

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 5640' PBD 5080' Perfs at 5014-19'

1st plug pump 1 sack hulls and 50 sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:15 pm Day: 12 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 5640' PBD 5080' Perfs at 5014-19'

1st plug pumped 1 sack hulls and 50 sx cement to bottom, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

Maximum pressure 500 pis and shut in 200 spi

Remarks: Used 60/40 Pozmix 2% gel by Halliburton Rec 3072' of 5 1/2"
(If additional space necessary, use BACK of this form.)

INVOICED
DATE 12-26-84
INV. NO. 6163

RECEIVED
DEC 18 1984
12-18-84
CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthi
(TECHNICIAN)