

To: 1051889 1-20
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,428-0000
NW SE NW, SEC. 6, T 31 S, R 31 W/EK
3460 feet from S section line
3866 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293

Lease Name Schmidt Well # B-2

Operator: Helmerich & Payne, Inc.

County Seward 86,97

Name & Address P.O. Box 558

Well Total Depth 2676 feet

Garden City, KS 67846

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 622

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address _____

Company to plug at: Hour: 10 a.m. Day: 20 Month: 1 Year: 19 95

Plugging proposal received from Allen Dick

(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 5 1/2" at 2675' circulated with 525 sx cement, PBD 2674', Perfs at 2648-2660'

1st plug pump 200 lbs. hulls mixed in with 40 sx cement down 5 1/2", displace to 2100',

2nd plug run tubing to 750' and pump 50 sx cement down tubing, circulate to surface inside 5 1/2".

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 20 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls mixed in with 40 sx cement down 5 1/2", displaced to 2100',

2nd plug ran tubing to 750' and pumped 50 sx cement down tubing, circulating to surface inside 5 1/2".

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of THIS FORM.)

observe this plugging.

INVOICED

DATE 2-6-95

INV. NO. 42166

Signed Richard M. Luedtke JAN 24 1995
(TECHNICIAN)

CONSERVATION DIVISION
FORM MCP-2/3
Rev. 01-84