

15-175-60425-0000

11-16

API NUMBER 15- Completion date 10/27/55

To: 1020819  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW, SEC. 6, T 31 S, R 31 W/EX  
3960 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293  
Operator: Helmerich & Payne, Inc.  
Name & Address: P.O. Box 558  
Garden City, KS 67846

Lease Name Schmidt Well # B-1  
County Seward  
Well Total Depth 2748 89.31 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 578

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_  
Address Liberal, KS

Company to plug at: Hour: 8 a.m. Day: 16 Month: 11 Year: 19 94

Plugging proposal received from Ken Jehlik

(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 5 1/2" at 2747' w/300 sx cement, CIBP at 2660', Perfs at 2642-47'

1st plug pump 1 sx hulls and 150 sx cement at bottom,

2nd plug run tubing to 650' and pump 20 sx cement at 650'-450',

3rd plug pump 5 sx cement at 40-0',

4th plug pump 70 sx cement down 8 5/8" annulus.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 16 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 150 sx cement at bottom, pressured to 500#. TOC at 700'.

2nd plug ran tubing to 650' and pumped 20 sx cement at 650-450',

3rd plug pumped 5 sx cement at 40-0',

4th plug pumped 70 sx cement down 8 5/8" annulus. Pressured to 400#.

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

(If desired, observe this plugging.)

**INVOICED**

Signed Glenn R Barlow  
(TECHNICIAN)

DATE 12-6-94

INV. NO. 41821

RECEIVED  
STATE CORPORATION COMMISSION  
11-22-94  
NOV 22 1994