

To: 1,100198 2-13
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-175-21,226-00-00
NW NW SE, SEC. 11, T 31 S, R 31 W ~~XX~~
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30129
Operator: Eagle Creek Corporation
Name & Address 107 N. Market, Ste. 509
Wichita, KS 67202

Lease Name Geisinger Well # 2-11
County Seward 190.39
Well Total Depth 5858 feet
Conductor Pipe: Size 20" feet 63
Surface Casing: Size 8 5/8" feet 1653

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing Pulling Service License Number 6547
Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: _____ Day: 13 Month: 2 Year: 19 98

Plugging proposal received from Kirby Lillard
(company name) Sargents Casing Pulling Service (phone) 316-624-7455

Work: 4 1/2" at 5827' w/200 sx cement, PBD 5827', Perfs at 5434-5448'
1st plug spot 20 sx cement with 100 lbs. hulls at 5434', displace with mud,
2nd plug spot 50 sx cement at 1680', displace with mud,
3rd plug spot 40 sx cement at 650',
4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 13 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug spotted 20 sx cement with 100 lbs. hulls at 5434',
displaced with mud,
2nd plug spotted 50 sx cement at 1680', displaced with mud,
3rd plug at 650' with 40 sx cement,
4th plug at 40' with 10 sx cement.

RECEIVED
2-23-99
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargents. Recovered 1700' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
is a minimum observe this plugging.

DATE FEB 25 1999

INV. NO. 50132

Signed Gary Winters
(TECHNICIAN)