

1 031136

1-6

192 P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,161-0000

N/2 N/2 SW, SEC. 19, T 31 S, R 31 W/E

2310 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3855

Lease Name S.W. College Well # 2

Operator: P & M Petroleum Management

County Seward 182.00

Name & Address 1600 Broadway, Ste. 1700

Well Total Depth 5600 feet

Denver, CO 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1519'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Exeter Drilling Company License Number 3098

Address P.O. Box 17349, Denver, CO 80217

Company to plug at: Hour: 4 p.m. Day: 6 Month: 1 Year: 19 91

Plugging proposal received from Lewis Ledbetter

(company name) Exeter Drilling Company (phone) 303-861-0181

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1530' with 50 sx cement, 2nd plug at 750' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7 p.m. Day: 6 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,

2nd plug at 750' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

STATE CORPORATION COMMISSION
1-25-91
JAN 25 1991
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED (XXXX) (if not) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE FEB 13 1991

INV. NO. 30720 MAR 07 1991