

To: 1 020633 12-21
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,087 -0000112R
C SE NE, SEC. 28, T. 31 S, R. 31 W ~~XX~~
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3711
Operator: Shepler & Thomas, Inc.
Name & Address P.O. Box 1816
Liberal, KS 67905-1816

Lease Name Elliott Well # 28-1
County Seward
Well Total Depth 5950 193.38 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1607

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2:30 p.m. Day: 18 Month: 12 Year: 19 92

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 5645' w/150 sx cement, PBTD 5591', Perfs at 5496-5502, 5470-76'
1st plug pump 1 sx hulls and 25 sx cement at perfs,
2nd plug pump 30 sx cement at 1800', 3rd plug pump 40 sx cement at 1607',
4th plug pump 35 sx cement at 750',
5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 21 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs,
2nd plug pumped 30 sx cement at 1800',
3rd plug pumped 40 sx cement at 1607',
4th plug pumped 35 sx cement at 750',
5th plug pumped 10 sx cement at 40 to -4'.

Mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 1804' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 1-19-93
INV. NO. 37212

Signed Glenn Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1993