

1 010019

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A 15-007-22626-0000
NE SE NW, SEC. 30, T 32 S, R 12 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428
Operator: Graves Drilling Co., Inc.
Name & Address 910 Union Center,
Wichita, KS 67202

Lease Name Bloom Jacobs Well # 1
County Barber 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:00 am Day: 21 Month: August Year: 19 85

Plugging proposal received from Elmo Morgernstern
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4598' PBTD 4583' Perfs at 4524-35'
1st plug sand back to 4475' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:50 am Day: 21 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4475' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 750 psi and shut in 600 psi

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE AUG 28 1985

AUG 28 1985

Signed Jack P. Metz
(TECHNICIAN)

INV. NO. 9820

CONSERVATION DIVISION
Wichita, Kansas
SEP 24 1985

FORM CP-2/3
Rev. 01-84