

1050425

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,850-0000
NW SE, SEC. 11; T 31 S, R 22 W/E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6029
Operator: Ladd Petroleum Corporation
Name & Address P. O. Box 2848
Tulsa, OK 74101

Lease Name Giles Well # 2-11
County Clark 173.88
Well Total Depth 5350 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 715 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 29 Month: December Year: 19 84

Plugging proposal received from Eugene Saloga

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1200' with 50 sx cement

2nd plug at 750' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
STATE CORPORATION COMMISSION
(TECHNICIAN)

JAN 09 1985
None X

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 pm Day: 29 Month: December Year: 19 84
CONSERVATION DIVISION
Wichita, Kansas

ACTUAL PLUGGING REPORT 1st plug at 1200' with 50 sx cement, 2nd plug at 750' with
40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dowell
(If additional description is necessary, use BACK of this form.)

(XXXX) did not observe this plugging.

INVOICED
DATE 1-15-85
INV. NO. 6961

Signed Richard W. Lacey
(TECHNICIAN)
W. J. Solomon
FORM CP-2/3
Rev. 01-84