

To: 1 090242 12-29
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-21,090-0006
300' N & 100' W
of C NE, SEC. 12, T. 31 S, R. 22 W/EX
4620 feet from S section line
1420 feet from E section line
Lease Name Robert Giles Well # 1
County Clark 172.25
Well Total Depth 5300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 679

TECHNICIAN'S PLUGGING REPORT
Operator License # 9220
Operator: Benson-McCown & Company
Name & Address 1616 S. Kentucky, Bldg. C-305
Amarillo, TX 79102-2249

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241
Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 8 p.m. Day: 29 Month: 12 Year: 19 92

Plugging proposal received from Bill Owens
(company name) Emphasis Oil Operations (phone) 913-483-5345

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1480'
1st plug at 1490' with 50 sx cement,
2nd plug at 700' with 50 sx cement, 3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:45 p.m. Day: 29 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1480' with 50 sx cement,
2nd plug at 700' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 1-6-93
INV. NO. 37111

Signed _____ (TECHNICIAN)

15-025-21,090-000mail

State of Kansas

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: December 10, 1992

Spot 300' N & 100' W East
C NE/4 Sec 12 Twp 31 S Rg 22 West

OPERATOR: License # 9220
Name: Benson-McCown & Company
Address: 1616 S. Kentucky, Bldg C-305
City/State/Zip: Amarillo, TX 79102-2249
Contact Person: Carl H. Benson
Phone: (806)-353-7429

4260 feet from South North line of Section
1420 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License #: 8241
Name: Emphasis Oil Operations

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Clark
Lease Name: Robert Giles Well #: 1
Field Name:

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
GWD Disposal X Wildcat Cable
Seismic: # of Holes Other
Other
GWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Mississippi
Nearest lease or unit boundary: 300'
Ground Surface Elevation: 2140 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 150'
Depth to bottom of usable water: 180'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 725'
Length of Conductor pipe required: 40'
Projected Total Depth: 5350'
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well X farm pond other

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:
Bottom Hole Location:

Oil Permit #:
Will Cores Be Taken? yes X no
If yes, proposed zone:

Exp. 6/7/93

AFFIDAVIT

200' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

12-29-92 8:00 AM

Pusher Bill Owens
SPUD DATE 12-11-92 INIT. R.L.L
LENGTH SURFACE PLANNED 725

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8" @ 6 7/8" CONDUCTOR
ANHYDRITE T- B-1480 ELEVATION

TD 5300 FORMATION

RAN PIPE @ DV TOOL ALT II DONE
SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1480 Ft. W/ 50 SX

1/2 Base Anyh. @ Ft. W/ SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 700 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond
Hauling

TECHNICIAN SM DATE 12-28-92

TYPE OF CEMENT 6 8/40 670

STARTING TIME 8:00 (AM/PM) DATE 12 29 92

COMPLETION TIME 10:45 (AM/PM) DATE 12 29 92

CEMENT COMPANY 1588

RECEIVED
NON-COMMISSIONED