

1 010157

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,834-0000
C NW NE, SEC. 14, T 31 S, R 22 W/K
4620 feet from ~~N~~ SE Corner of section line
1980 feet from ~~W~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029
Operator: Ladd Petroleum Corporation
Name & Address P. O. Box 2848
Tulsa, OK 74101

Lease Name Giles Well # 2-14
County Clark 172.25
Well Total Depth 5300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 717

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 N. Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 1:00 am Day: 24 Month: September Year: 19 84

Plugging proposal received from E. J. Woody

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1020' with 50 sx cement

2nd plug at 725' with 50 sx cement

3rd plug ^{solid bridge} hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Ken Beakey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 am Day: 24 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd plug at 725' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

10-1-84

OCT 01 1984

CONSERVATION DIVISION

Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form.)

did not observe this plugging.

Signed Kenneth Beakey SD
(TECHNICIAN)

INVOICED

DATE 10-3-84

INV. NO. 4003