

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025 -20,792-0000
Approx. SW/4
SE/4 SE/4, Sec. 19, T 31 S, R 22 W/8

330 feet from ~~WS~~ section line

900 feet from ~~WE~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name Young Brothers Well # 1-19

Operator: Ladd Petroleum Corporation
Name & P. O. Box 2848
Address Tulsa, OK 74101

County Clark

Well Total Depth 5395 feet 175.34

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 785

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling License Number 5380

Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 2:00 am Day: 11 Month: June Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Butch Steinert

(company name) Eagle (phone) 316-672-6639

were: fill hole with heavy mud and spot cement through drill pipe

1st plug at 960' with 50 sx cement

2nd plug at 496' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement
Signed *Phyllis Wiley*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 4:45 am Day: 11 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 960' with 50 sx cement, 2nd plug at 496' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement

Remarks: Used 60/40 Pozmix 2% gel 3% cc

RECEIVED
STATE CORPORATION COMMISSION
6-14-84
JUN 14 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed *Phyllis Wiley*
(TECHNICIAN)

INVOICED
DATE 6-26-84
INV. NO. 2147
6-11