

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 3 Twp. 30S Rge. 7 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NE NE

Lease Owner Pickrell Drilling Company
Lease Name Well WULF Well No. 2
Office Address 110 N. Market, Suite 205, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)


OIL

Date Well completed 6-27 1965
Application for plugging filed 6-4- 1979
Application for plugging approved 6-5- 1979
Plugging commenced 7-28- 1979
Plugging completed 8-1-2:00 1979
Reason for abandonment of well or producing formation
Depleted

If a producing well is abandoned, date of last production
5-10 1976

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation Mississippi Depth to top 4112 Bottom Total Depth of Well 4210
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Oil & Water	4143	4155	8 5/8"	250	NONE
				4 1/2"	4209	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
 feet for each plug set.

TD - 4210
Float cellar 4178
Sand from 4178 to 4060
4 sacks cement 4060 to 4020

Bridge at 250 - Rock 240
4 1/2 yard ready mix to top

RECEIVED
STATE CORPORATION COMMISSION
10-2-79
OCT - 2 1979

CONSERVATION DIVISION
110 N. Market

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barker, ss.
Elinor R. Margenstern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Elinor R. Margenstern
Medicine Lodge, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of August, 1979

Jessie Hamilton
Notary Public.

My commission expires April 4, 1982

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 6/28/58

LOCATION: SE NE NE Sec. 3-30S-7W
 Kingman County, Kansas

Rotary Drilling Completed 7/9/58

CONTRACTOR: Wulf #2
PICKRELL DRILLING COMPANY
 Wichita, Kansas

CASING RECORD: 240' (6 jts.) 8-5/8" 22.7# Armco Spiralweld Casing cemented with 115 sacks cement. Cement circulated.
 4-1/2" 9.50# J-55 Smls. Casing set at 4209' cemented with 100 sacks cement.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Red rock, Shale & Shells	940'	Circ. for samples at 4110'
Shale, Shells & Lime	1220'	4129'
Lime & Shale	1595'	4138'
Lime & Sand	1710'	4160'
Lime & Shale	2420'	4210'
Lime	2510'	
Lime & Shale	3242'	
Lime, Shale & Sand	3356'	
Lime	3985'	
Lime & Shale	4110'	
Mississippi	4210' T.D.	

S.L.M. at 1500 - O.K.
 2500 - O.K.
 3500 - O.K.

Slope Test at 1500 0° off
 2500 0° off
 3500 0° off

RECEIVED
 STATE CORPORATION COMMISSION
 JUN - 6 1979
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By *C. W. Sebitts*
 Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 17 th day of July, 1958, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: October 13, 1960

Lorraine Johnson
 Notary Public