


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 2 Twp. 30 Rge. 7 (X) (W)

Location as "NE/CNW/SW" or footage from lines NW SW NE
Lease Owner H.C. Bennett
Lease Name Krehbiel Well No. A-7
Office Address 1212 Union Nat'l Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 1-18-59 19
Application for plugging filed 9-5-66 19
Application for plugging approved 9-6-66 19
Plugging commenced 9-9-66 19
Plugging completed 9-13-66 19
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Herman Justice
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4212 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	211'	none
				5 1/2	4177'	3490'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with chat from 4212' to 4170' and dump 5 sacks of cement
Set 15' rock bridge from 250' to 235' and dump 25 sacks of cement
Mud hole to 40' and dump 10 sacks of cement to surface

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Const. Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *James Davis*

(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of September, 19 66

Ronald P. Hanson

Notary Public.

My commission expires September 27, 1967

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 1-7-59

Rotary Drilling Completed 1-18-59

LOCATION: NW NW NE Sec. 2-306-7W
Kingman County, Kansas

CONTRACTOR: Krehbiel "A" #1
PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 211' (8 jts.) of 8-5/8" J-55 2 1/2" Sals. casing set with 100 sacks cement. Cement circulated.
5-1/2" (129 jts.) 1 1/2" casing set at 4177' with 100 sacks cement.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Sand	5'
Clay	10'
Sand & Clay	20'
Red Rock	210'
Red Rock & Shale	640'
Shale	1070'
Shale & Lime	1250'
Lime	1370'
Lime & Shale	1505'
Lime	1640'
Lime & Shale	3180'
Lime, Sand & Shale	3330'
Lime	3493'
Lime & Shale	3575'
Lime	3800'
Lime & Shale	4088'
Mississippi	4180' T.D.

Circ. fro samples at
 4100'
 4112'
 4117'
 4123'
 4130'
 4180'

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1966

CONSERVATION DIVISION
Wichita, Kansas

S. L. M. at 2000 - O.K.
3000 - O.K.
3800 - O.K.

Slope Test at 2000 - 0° off
3000 - 0° off
3900 - 0° off

*open hole 4177' - ~~4180'~~
2-D - 4212'*

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. Sebitts
Attorney-in-Fact

STATE OF KANSAS } ss.:
COUNTY OF SEDGWICK }

On this 20th day of January, 19 59, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires 1962

Mary Ellen Sampson
Notary Public
(Mary Ellen Sampson)