

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Kingman County, Sec. 2 Twp. 30S Rge. 7W (E) (W)

Location as "NE/CNW/SW" or footage from lines C-NW-SW

Lease Owner Union Oil Company of California

Lease Name Sankey Coberly Well No. 1

Office Address 7th Floor So. Bldg. 2000 Classen Center - Okla. City, Ok.

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed Jan. 11 19 56

Application for plugging filed Dec. 12 19 66

Application for plugging approved Dec. 13 19 66

Plugging commenced Feb. 17 19 67

Plugging completed Feb. 23 19 67

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production Sept. 27 19 65

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. Elving

Producing formation Mississippi Depth to top 4154' Bottom 4164' Total Depth of Well 4246 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Oil	4154'	4164'	8-5/8"	268'	None
Kansas City	SWD Zone	3804'	3828'	5-1/2"	4245'	2706'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from (1) feet to feet for each plug set.

(1) Halliburton pumped 10 sacks cmt. into perf's. in 5 1/2" casing 4154'-4164' @ 900# pressure, then spotted 65 sx. cmt. plug across perf's. in 5 1/2" casing 3804'-3828', checked top of cmt. inside 5 1/2" casing @ 3808', pressure up on casing to 1000# - held OK. Spotted 25 sx. cmt. plug from 3808' to 3650'. Shot casing @ 3550', 3350', 3280', 3180', 3008' & 2902' pulled 3000# tension on 5 1/2" casing after each shot, pipe would not come free. Shot csg. off @ 2706' pulled 3000# tension on 5 1/2" casing & pipe came free, recovered 81 jts. 5 1/2" OD 14# J-55 casing for 2706'. Mudded hole from 2706' to 250', spotted rock bridge from 250' to 240', spotted 25 sx. cmt. plug from 240' to 40', drilling mud from 40' to 30', Rock bridge from 30' to 20', spotted 10 sx. cmt. plug from 20' to 4'. Cut 8-5/8" casing off 4' below ground level, filled cellar & leveled location. Well plugged & abandoned.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Noel Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
C. R. Pierce (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Pierce Dist. Prod. Supt.
7th Floor South Bldg. - 2000 Classen Center
Oklahoma City, Oklahoma 73106
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 19 67

My commission expires April 14, 1968

John H. [Signature] Notary Public.