

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

KINGMAN County, Sec. 1 Twp. 30 Rge. 7 W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NW NE SW

Lease Owner PICKRELL DRILLING COMPANY
Lease Name REIDA Well No. 2
Office Address 205 LITWIN BUILD., 110 N Market, Wichita
Character of Well (Completed as Oil, Gas or Dry Hole)

OIL

Date Well completed 2-18 1960
Application for plugging filed 3-26 1979
Application for plugging approved 3-27 1979
Plugging commenced 4-17 1979
Plugging completed 4-21 1979
Reason for abandonment of well or producing formation

Depleted

If a producing well is abandoned, date of last production
9-1 1978

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? YES ~~YES~~

Name of Conservation Agent who supervised plugging of this well BILL OWENS
Producing formation Mississippi Depth to top 4112 Bottom Total Depth of Well 4200
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Oil & Water	4114	4124	8 5/8 5/2"	240 4197	NONE 3339

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

ALLIED PUMPED IN 35 SACKS CEMENT. PLUGGED OFF PERFORATIONS. WOODEN BRIDGE
AT 240. ROCK TO 230. 5 YARDS READY MIX.

RECEIVED
STATE CORPORATION COMMISSION

OCT - 2 1979
10-2-79

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor CLARKE CORPORATION

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack Gurley (employee of ~~owner~~ or ~~operator~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

110 N. Market, Suite 205, Wichita, Ks. 67202
(Address)


SUBSCRIBED AND SWORN TO before me this 1st day of October, 1979

Carlene Lee

Notary Public.

My commission expires March 8, 1983

Carlene Lee



File 1-9-60
ROTARY DRILLING LOG

15-095-01091-0000

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas

LOCATION: Reida #2
NW NE SW Sec. 1-30-7W
Kingman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

Rotary Drilling Commenced 1-9-60
Rotary Drilling Completed 1-23-60

CASING RECORD: 8-5/8" spiral csg. set @ 240' w/140 sacks - 2% gel. - 2% C.C.

Ran 132 jts. 15.5# SMLS. 8rd. J-55 CF&I csg. 5 1/2" csg. set at 4196.74 cemented w/90 sacks at 2% gel. cement.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

	40 Sand		Circ. for samples:
	170 Red Beds		
	240 Shale	4100'	
	290 Red Rock	4110'	
	885 Red Rock, shale & shells	4130'	
	985 Shale & shells & salt	4140'	
	1010 Anhydrite	4145'	
	1270 Shale, shells	4160'	
	1435 Lime & shale	4200'	
	1680 Lime		
	3045 Lime & shale		
	3355 Sand, shale & lime		
	3655 Lime & shale	Slope Test:	
	3725 Lime		
	4105 Lime & shale	2000'	0°
	4200 Mississippi	3000'	0°
	4200 Rotary Total Depth	4000'	0°
		S.L.M.	
		2000'	OK
		3000'	OK
		4000'	OK

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1979
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By *C. W. Sebitts*
C. W. Sebitts, Partner

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 26th day of January, 19 60, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written

Ruth M. Sullivan
Notary Public
Ruth M. Sullivan

My commission expires: August 13, 1961