

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-21623-00-00

LEASE NAME MAPLE

WELL NUMBER 3

1850 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 1 TWP. 30 RGE. 7W (E) or (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 6-16-03

Plugging Completed 6-18-03

RECEIVED
JUN 26 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ABERCROMBIE ENERGY LLC

ADDRESS Rt. 1 Box 56 Great Bend, Kansas 67530

PHONE# (620) 793-8186 OPERATORS LICENSE NO. 32457

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well

Plugging proposal was approved on _____ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.O. 4185'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	261'	None
				5-1/2"	4183'	3000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 4050' and 5 sacks cement. Cut casing off @3000', pulled up to 1100', pumped 100# hulls and 35 sacks cement, pulled up to 700', pumped 100# hulls and 35 sacks cement, pulled up to 325' and circulated 80 sacks cement to surface 60/40 pos. 4% gel. Layed rest of casing down. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Energy LLC

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 24th day of June, 20 03

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Notary Public