


All Information Completely
Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec 1 Twp. 30S Rge. 7W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner Pickrell Drilling Company
Lease Name Reida Well No. 3
Office Address 2820 Paseo Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19____
Application for plugging filed May 3, 1963 19____
Application for plugging approved May 4, 1963 19____
Plugging commenced May 6, 1963 19____
Plugging completed May 8, 1963 19____
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4152 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	254	none
				5 1/2	none	3547

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved on, cleaned out cellar and sanded to 4090'. Dumped 5 sx. cement and worked pipe.

Worked pipe and shot @ 3620'-3525'. Pulled pipe.

Finished pulling pipe and plugged well with mud. Built rock bridge @ 225' and dumped 20 sx. cement. Filled hole and rock bridge and capped well with 10 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 1963

Carolyn Herren
Notary Public.

My commission expires July 23, 1966

ROTARY DRILLING LOG

15-095-01344-0000

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita 2, Kansas
LOCATION: REIDA #3 - NW SW SW, Sec. 1-30S-7W,
Kingman County, Kansas

Rotary Drilling Commenced 8/21/61
Rotary Drilling Completed 9/1/61

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 254' (6 jts.) 8 5/8" 20# surface casing w/150 sacks cement. Circulated.
4189' (133 jts.) 5 1/2" 14# Smls. casing cemented w/100 sacks cement.
Completed 9:30 A.M. 9/1/61

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>	
254'	Red Rock & Shale	4108'	
755'	Red Rock & Blue Shale	4110'	
1128'	Shale & Shells	4130'	
1615'	Lime	4135'	
2805'	Lime & Shale	4145'	
2992'	Lime, Sand & Shale	4155'	
3286'	Lime & Shale	4191'	
3792'	Lime		
4091'	Lime & Shale	<u>Slope Test</u>	
4191'	Mississippi R.T.D.	1615'	0°
		2520'	0°
		3792'	0°
		4155'	0°
		<u>S. L. M.</u>	
		2155'	
		3286'	
		4091'	

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1963

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS
COUNTY OF SEDGWICK

On this 7th day of September, 1961, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Witness my hand and the seal of office this day and year last above written.
September 24, 1962
Maxine Johnson
Maxine Johnson, Notary Public