


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 35 Twp. 30S Rge. 6W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Comet Petroleum Corporation
Lease Name Hunter Well No. 1
Office Address 608 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 2 19 69
Application for plugging filed July 2 19 69
Application for plugging approved July 2 19 69
Plugging commenced July 2 19 69
Plugging completed July 2 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4583 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with heavy mud to 240' from surface, 1/2 sack hulls, plug and 25 sacks cement. Heavy mud to 40' of surface, 1/2 sack hulls, plug and 10 sacks cement. 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don Gardner (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
300 Schweiter Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of July, 19 69

My commission expires December 14, 1969

Notary Public.

DRILLERS LOG

#1 HUNTER
 C. SE NE Section 35-30S-6W
 Kingman County, Kansas

OPERATOR: Comet Petroleum Corporation
 608 Union Center
 Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
 300 Schweiter Building
 Wichita, Kansas

COMMENCED: June 19, 1969

COMPLETED: July 2, 1969

CASING RECORD: 8-5/8" @ 240' w/225 sacks

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	100	Shale and sand
100	245	Red Rock and shale
245	940	Shale and shells
940	1360	Shale and lime
1360	1690	Lime
1690	3625	Lime and shale
3625	3690	Lime
3690	3767	Lime and shale
3767	3845	Lime
3845	4123	Shale and lime
4123	4245	Lime
4245	4552	Lime and shale
4552	4583	Lime
4583		Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 9 1969
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)


I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.


 Don Gardner

Subscribed and sworn to before me this 8th day of July, 1969.

My commission expires:
 December 14, 1969


 Notary Public