


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Kingman County. Sec. 33 Twp. 30S Rge. (E) 6W (W)
Location as "NE/CNW'SW'" or footage from lines C SW NE
Lease Owner: The National Oil Company
Lease Name Van Geison Well No.]
Office Address 200 W. Douglas, Suite 550, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-14 1973
Application for plugging filed 1-14 1973
Application for plugging approved 1-14 1973
Plugging commenced 1-14 1973
Plugging completed 1-14 1973
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well G. Russel Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4672 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	208'	8-5/8"	202'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 175', plug, 35 sx cement;
Fluid to 40, plug, 10 sx cement;
Two sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor D N B DRILLING, INC.
Address 701 First National Bank Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 73

My commission expires August 25, 1976

Ella Priess
Ella Priess
Notary Public.

DRILLERS' LOG

THE NATIONAL OIL COMPANY
No. 1 Van Geison
C. SW NE, Sec. 33-30S-6W
Kingman County, Kansas

Elevation: 1545 K.B.

Commenced: 12-31-72
Completed: 1-14-73

Surface Casing: 202/ of 8-5/8"
cemented w/200 sx 50-50 Posmix,
3% cc. 12-31-72

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 208
Red Bed	208 - 509
Shale	509 - 850
Salt & Shale	850 - 1100
Lime & Shale	1100 - 1245
Lime	1245 - 1290
Shale & Lime	1290 - 1640
Lime & Shale	1640 - 2030
Shale & Lime	2030 - 2212
Lime & Shale	2212 - 2400
Lime	2400 - 2460
Lime & Shale	2460 - 2622
Shale & Lime	2622 - 3487
Sand & Shale	3487 - 3564
Shale & Lime	3564 - 3727
Lime	3727 - 3922
Lime & Shale	3922 - 4215
Lime	4215 - 4540
Lime & Shale	4540 - 4575
Lime	4575 - 4608
Shale	4608 - 4672 T.D.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1973
CONSERVATION DIVISION
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 17th day of January, 1973.

My Commission Expires:
August 25, 1976

Ella Priess
Ella Priess, Notary Public

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976