


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

KINGMAN County, Sec. 13 Twp. 30S Rge. (E) 7 (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner DRILLER'S PRODUCTION CO., INC.
Lease Name BODINE Well No. 1
Office Address 1020 UNION NATIONAL BLDG., WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 8-31-59 1959
Application for plugging filed (PHONE - 8-31-59) 1959
Application for plugging approved (PHONE - 8-31-59) 1959
Plugging commenced 8-31 1959
Plugging completed 8-31 1959
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRED HOMPLE
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4210 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	2516'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 240 FEET. SET FIRST PLUG AT 240 FEET WITH 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG AT 40 FEET WITH 10 SACKS CEMENT. JOB COMPLETED 5:00 P.M. 8-31-59

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1959 9-14-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES DRILLING CO., INC.
Address 512 ORPHEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
H. F. JONES (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. F. Jones
514 ORPHEUM BLDG., WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 11TH day of SEPTEMBER, 1959

[Signature]
Notary Public.

My commission expires 11-19-62



PLUGGING

File Sec. 13 T 30 R 7a
Book Page 3 Line 10

GABBERT-JONES DRILLING CO., INC.

WICHITA, KANSAS

DRILLER'S WELL LOG

BODINE #1
C NE SW SECTION 13-30S-7W
KINGMAN COUNTY, KANSAS
COMMENCED: AUGUST 19, 1959
COMPLETED: AUGUST 31, 1959

OPERATOR - DRILLER'S PRODUCTION CO., INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	130	RED BED	
130	225	SHALE AND SAND	
225	250	RED BED	RAN 251.6' OF 8-5/8" CASING, CEMENTED @ 250' W/225 SACKS CEMENT.
250	960	SHALE AND SHELLS	
960	990	ANHYDRITE	
990	1110	SHALE AND SHELLS	
1110	1250	ANHYDRITE	
1250	1350	SHALE AND LIME	
1340	1510	SANDY LIME	
1510	1720	LIME	
1720	1775	LIME AND SHALE	
1775	1855	SHALE AND SHELLS	
1855	2150	LIME AND SHALE	
2150	2375	SHALE AND SHELLS	
2375	2508	SHALE AND LIME	
2508	2690	SHALE AND SHELLS	
2690	2875	SHALE AND LIME	
2875	3040	BROKEN LIME	
3040	3096	LIME AND SHALE	
3096	3215	SAND AND SHALE	
3215	3360	LIME AND SHALE	
3360	3450	LIME	
3450	3550	LIME AND SHALE	
3550	3809	LIME	
3809	4106	LIME AND SHALE	
4106	4142	CHERT	
4142	4210	LIME AND CHERT	
4210	TD		DRY AND ABANDONED

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1959
CONSERVATION DIVISION
Wichita, Kansas

I, H. F. JONES, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE BODINE #1.

H. F. Jones
H. F. JONES

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 8TH DAY OF SEPTEMBER, 1959 PERSONALLY APPEARED H. F. JONES, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HERewith SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Emmet E. Hall
EMMET E. HALL, NOTARY PUBLIC

MY COMMISSION EXPIRES 11-19-62

PLUGGING

File Sec. 13 T 30 R 7W

Book Page 2 Line 10