

SIDE TWO

Operator Name Pan Eastern Exploration Co. Lease Name GASKILL "B" Well # 1H

Sec. 10 Twp. 33S Rge. 38 East West County Stevens **RELEASED**

WELL LOG

MAR 0 6 1990

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

FROM CONFIDENTIAL

Drill Stem Tests Taken Yes No
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No

Formation Description
 Log Sample


Name	Top	Bottom
Shale	0'	105'
Shale, Redbed	105'	616'
Redbed	616'	1090'
Shale	1090'	1205'
Glorita Sand	1205'	1378'
Shale	1378'	1390'
TD		1390'

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24#	618	75/25 Poz Common	170 150	2% CC 3% CC
PERFORATION RECORD				Acid, Fracture, Shot, Cement Squeeze Record			
Shots Per Foot	Specify Footage of Each Interval Perforated			(Amount and Kind of Material Used)		Depth	
TUBING RECORD				Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No			
Date of First Production		Producing Method <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (explain).....					
Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio	Gravity		
	Bbls	MCF	Bbls	CFPB			

METHOD OF COMPLETION

Production Interval

Disposition of gas: Vented Open Hole Perforation
 Sold Other (Specify) R&A
 Used on Lease Dually Completed
 Coningled



BW

RELEASED

MAR 06 1990

GABBERT-JONES, INC.
WICHITA, KAS.

FROM CONFIDENTIAL

DRILLERS WELL LOG

GASKILL B-1H
C NW/4 Sec. 10-33S-38W
Stevens County, Kansas

COMMENCED: 7-20-87

COMPLETED: 7-26-87

OPERATOR: ANADARKO PETROLEUM CORP.


DEPTH		Formation	Remarks
From	To		
0	105	Shale	Ran 14 jts. of 24# 8 5/8"
105	616	Shale-Redbed	csg. set @ 616' w/220 sks.
616	1090	Redbed	75/25 Posmix 2% CC - 1/4#
1090	1205	Shale	Floseal - 150 sks Common
1205	1378	Glorita Sand	3% CC - 1/4# Floseal
1378	1390	Shale	PD @ 9130 AM 7-21-87.
	1390 TD		1360' - 50 sks Class H 4% Hilit - 12 1/2# Gilsonite - 1/2# Floseal 3% CC - 100 sks Class H - 12 1/2# Gilsonite 1/2# Floseal 4% CC. CP @ 11:00 PM 7-22-87.
			1st 75 sks @ 630' 2nd 20 sks @ 40' 10 sks in rathole - 60/40 Posmix 2% CC. CP @ 10:00 AM 7-26-87.

STATE OF KANSAS) I, the undersigned, being duly sworn on oath, state that
) the above Drillers' Well Log is true and correct
COUNTY OF SEDGWICK) to the best of my knowledge and belief and according
) to the records of this office.

KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

SEP 21 1987

GABBERT-JONES, INC.


James S. Sutton, II - President

Subscribed & sworn to before me this 3rd day of August 1987


Lola Lenore Costa - Notary Public

My Commission expires 11-21-88

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1987

CONSERVATION DIVISION
Wichita, Kansas