

RECEIVED

MAY 20 2002

Not a well  
Recommended

KCC WICHITA

5-20-02

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-095-205640001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003  
(owner/company name) (operator's)  
ADDRESS 453 S. Webb Rd. P.O. Box 780208 CITY Wichita  
STATE Kansas ZIP CODE 67278 CONTACT PHONE # (316) 636-2737

LEASE Kohman WELL# 2 SEC. 8 T. 30S R. 7 (East/West)

SW - - SW - - NW - - SPOT LOCATION/QQQQ COUNTY Kingman

2970 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

4950 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8 SET AT 215 CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 4178 CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Krider 1356-1364 and 1346-1350 CIBP 3970

ELEVATION 1485 1495 T.D. PBD 1416 ANHYDRITE DEPTH CIBP 3690  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand or CIBP to 1300'. Pull stretch & cut casing. Pull casing to 700', spot 35 sx. Pull csg to 270', circulate to surface. Pull csg & top off cement. 60/40, 4% gel. (5 sx cement f/ sand, 1 sk cement f/ CIBP)

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? No copies

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE# ( ) 620-272-1296

ADDRESS P.O. Box 39 City/State Spivey, KS 67142

PLUGGING CONTRACTOR Shawnee Well Service KCC LICENSE # 30346 3/03  
(company name) (contractor's)

ADDRESS Attica, KS 67009 PHONE # ( ) 620-243-4457

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5/17/02 AUTHORIZED OPERATOR/AGENT: Scott Dampel  
(signature)



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

McCoy Petroleum Corporation  
453 S. Webb Rd. STE 310  
PO Box 780208  
Wichita, KS 67278-0208

August 05, 2002

Re: KOHMAN #2  
API 15-095-20564-00-00  
CSWSWNW 8-30S-7W, 2970 FSL 4950 FEL  
KINGMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor

District: #2  
130 S. Market, Room 2125  
Wichita, KS 67202-3208  
(316) 337-6231