

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED
JAN 04 2002
KCC WICHITA

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

1-4-02

15-095-21188-00 ⁰¹

API NUMBER _____
LEASE NAME Kohman
WELL NUMBER 5 - 8
4950 ft. from S Section Line
330 ft. from E Section Line
SEC. 8 TWP. 30 RGE. 7 (E) or (W)
COUNTY Kingman
Date Well Completed _____
Plugging Commenced 12/5/01
Plugging Completed 12/7/01

LEASE OPERATOR McCoy Petroleum Corp.
ADDRESS 453 S. Webb Rd., Suite 310, Box 780208, Wichita, KS
PHONE # (620) 636-2737 OPERATORS LICENSE NO. 5003
Character of well oil

(Oil, Gas, D&A, SWD, input, Water Supply Well)
The plugging proposal was approved on 12/5/01 (date)
by Doug Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4250
Show depth and thickness of all water, oil and gas formations
OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	254	none
				4 1/2	4248	2833

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Sand at 4100, baled 4 sks cem. Shot pipe at 3010, 2833, worked pipe loose. Pulled to 1250, well blew out. Pump 35 cks cem. at 1250, pulled to 700, pump 35 sks cem. Pulled to 310, pump 85 sks cem. Circulated and pulled rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corp.
STATE OF Kansas COUNTY OF Sedgwick, ss.


Scott Hampel (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Scott Hampel
(Address) 453 S Webb Rd., Ste 310, POBox780208
Wichita KS 67278

SUBSCRIBED AND SWORN TO before me 3rd day of January, 2002

My commission Expires: 9/5/2002

Karen E. Houseberg
Notary Public



Form CP-4
Revised 05-88

OK

Quality Well Service, Inc.
401 West Main
Lyons, KS 67554

RECEIVED
 JAN 04 2002
 MCC WICHITA

Invoice

Date	Invoice #
12/12/2001	230

Bill To
McCoy Petroleum Corporation Box 2250 Garden City, KS 67846

DEC 27

P.O. No.	Terms	Lease Name
	net	Kohman #5

qty	Description	Rate	Amount
19	Rig Time	120.00	2,280.00T
	Trucking	90.00	90.00T
	Sand	35.00	35.00T
4	Cement	9.00	36.00T
2	Shots	135.00	270.00T
	Torch	35.00	35.00T
5	Water Truck	55.00	275.00T
	Out of Town	240.00	240.00T
	Gas	15.00	15.00T
	Phone Calls	5.00	5.00T
	Clerical Fees	10.00	10.00T
	fresh water	10.00	10.00T
	12/5/01 - 1 1/2 hrs. Moved from Attica. Looked for well, couldn't find it. Drove in.		
	12/6/01 - 12 hrs. Drove to location, rigged up pole. Checked hole, loaded hole. Ran sand, backhoe dug pit and cellar. Set floor, wated on sand to fall. Checked hole, sand at 4100, baled 4 sacks cement. Pulled slips, cut casing head off, had 21" minimum. Shot pipe at 3010, worked pipe. Shot pipe at 2833, worked pipe loose and pulled up to 1250. Well blew out. Cleaned up rig and drove in.		
	12/7/01 - 5 1/2 hrs. Drove to location, cleaned rig up. Got fresh water. Pumped 35 sacks cement at 1250, pulled to 700'. Pumped 35 sacks cement. Pulled to 310, pumped 85 sacks cement. Circulated and pulled rest of pipe. Tore down and loaded out.		

Subtotal	\$3,301.00
Sales Tax (5.9%)	\$194.76
Total	\$3,495.76

--

MCCOY PETROLEUM CORP
 ONE MAON PLACE #410 WICHITA, KS 67202
 CONTR SWEETMAN DRILLING INC CTY KINGMAN #5 KOHMAN 8-30-7W C E/2 NW NW

GEOL _____ FIELD SPIVEY-GRABS
 E 1523 KB CM 11/5/81 CARD ISSUED 12/10/81 IP P 19 BO & 85% WTR,

+	+
+	+
+	+

API 15-095-21,188

& 85MCFGPD,
MISS 4150-70

LOG	TOPS	DEPTH	DATUM
HEEB		3152	-1629
LANS		3368	-1845
KC		3636	-2113
STARK SH		3784	-2261
HERTHA		3824	-2301
CHER		4033	-2510
MISS		4146	-2623
RTD		4250	-2727
LTD		4251	-2728

8 5/8" 254/225sx, 4 1/2" 4248/125sx
 DST (1) 3812-30(HERTHA)/30-45-60-60
 370' GSY SO SPKD MSW, 124' GSY SW
 SIP 1054-1054#, FP 83-138/167-
 232#
 DST (2) 4147-75(MISS)/30-45-60-60.
 65'M. (2ND OP) GTS/3", GA 6.7MCFG
 /30" REC 65'M. SIP, 1054-1054#
 FP 40-56/56-74#

(OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

Property of Ks Corp Comm

MCCOY PETROLEUM CORP WICHITA KS 67226 #5-8 KOHMAN OWWO 8-30S-07W C E/2 NW NW

site: 1 W OF RAGO KS contr: SHAWNEE WELL SVC geol: NONE
 drlg comp 09/01/97 card issued 08/24/98 last revised 08/24/98
 site: KINGMAN field: SPIVEY-GRABS-BASIL API 15-095-21188

+	+
+	+
+	+

ELV: 1523 KB, 1513 GL LOG

tops	depth/datum
HEEB	3152 -1629
LANS	3368 -1845
KC	3636 -2113
STARK	3784 -2261
HERTHA	3824 -2301
PBTD	3950 -2427
CHER	4033 -2510
MISS	4146 -2623
RTD OLD	4250 -2727
LTD OLD	4251 -2728

IP status:
 INJ, LKC 3824-3828 , 09/03/97
 OLD INFO: OPERATOR WAS MCCOY PETROLEUM CO,
 5 KOHMAN, SPD 11/05/81 , 11/14/81 8-5/8" 254 / 225 SX,
 4-1/2" 4248 / 125 SX, OIL/GAS, P 19 BO & 108 BWPD &
 85 MCFGPD, MISS 4150-4170 , 11/25/81 (CARD ISSUED
 12/10/81)
 CONTR: SWEETMAN DRILLING
 NO CORES
 DST (1) 3812-3830 (LKC), / 30-45-60-60, REC 370' GSY
 SLI OIL SPKD MSW, 124' GSY SW ISIP 1054# FSIP
 1054# IFP 83# -138# FFP 167# -232#

COPYRIGHT 1998
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

(over)