

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR Robert F. White Lic # 5061 API NO. 15-025-20-455 00-00
 ADDRESS 505 Union Center, Wichita, KS 67202 COUNTY Clark
 FIELD McKinney
 **CONTACT PERSON same LEASE Theis #2
 PHONE (316) 263-7957

PURCHASER Northern Natural Gas Company WELL NO. 2
 ADDRESS 2223 Dodge St. WELL LOCATION NW/4 NW/4 ,or,
Omaha, Nebraska 68702 660 Ft. from North Line and
 660 Ft. from West Line of
 the ~~NW/4~~ SEC. 18 TWP. 34S RGE. 24W

DRILLING CONTRACTOR Rine Drilling Company
 ADDRESS Wichita, KS

PLUGGING CONTRACTOR _____
 ADDRESS _____

TOTAL DEPTH 5722' PBD 5614
 SPUD DATE 9-3-81 DATE COMPLETED 2-15-82
 ELEV: GRL979' DF - KB 1991'



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

KCC ✓
 KGS ✓
 MISC. _____

DRILLED WITH (ROTOR) (ROTARY) (A+B) TOOL:
 Report of all strings set - surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft	Setting depth	Type cement	Shots	Type and percent additives
Surface	10 3/4"	8 5/8"	23#	819	Common	450	---
Long string	7 7/8"	4 1/2"	10 1/2#	5722'	Pozmix	150	10% salt

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Shots cement	Shots per ft.	Size & type	Depth interval
			2/ft.	premium	5522'-26'
			2/ft.	premium	5528'-35'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	
Treated perforations with 12,000 gals 75% quality foamed acid consisting of 3,000 gals 28% HCL acid, 242,000 S.C.F. Nitrogen & foaming agent.	RECEIVED STATE CORPORATION COMMISSION 6-17-82 JUN 17 1983 CONSERVATION DIVISION Wichita, Kansas

TEST DATA:					PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity				
2-15-82	Flow					
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio		
	0 bbl	500 MCF	No bbl	N/A		
Disposition of gas treated, used, in lease or sold:			Producing interval:			
Sold			above			

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

of lowest fresh water producing stratum Unknown Depth 700
 Estimated height of cement behind pipe to surface

WELL LOG

Show all important zones of porosity and contents thereof; core intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
---------------------------------------	-----	--------	------	-------

Robert F. White

#2 G THEIS

13-35S-26W
 Meade County, Kansas

Contractor: RINE DRILLING COMPANY

Started: September 3, 1981


Completed: September 18, 1981

LOG

Surface	0 - 107'	
Red bed	107 - 2205'	TOICO - 3/4" @ 250', 1" @ 500' 1 1/2" @ 825' Ran 20 jts. 8 5/8" csg., set @ 819' cmt. w/300 sx. HalibLight + 2% + 1/4# Floseal + 150 sx. Class H + 3% c.c. Plug down @ 2:30 p.m. 9-5-81
Red bed & Anhydrite	2005 - 2250'	
Anhydrite	2250 - 3060'	TOICO - 1 1/2" @ 2275'
Dolomite	3060 - 4026'	
Lime & Shale	4026 - 5722'	TOTOO - 1/2" @ 4920', 1/2" @ 5722' Ran 150 jts. 4 1/2" csg., set @ 5722' cmt. w/150 sx. 60/40 poz, 10% salt + 1/4# Floseal + 2% gel. Plug down @ 12:15 a.m.

STATE OF KANSAS)
) SS:
 SEDGWICK COUNTY)

I, E.J. Rine, do hereby certify that the above is a true and accurate Log of the #2 G THEIS, located 18-34S-24W, Meade County, Kansas.


 E.J. Rine, President

Subscribed and sworn to before me this 28th
 day of September, 1981.


 Donna K. McKee, Notary Public

My appointment expires: 1-21-85



COPY

RECEIVED
 STATE CONSERVATION COMMISSION

JUN 17 1983

CONSERVATION DIVISION
 Wichita, Kansas