


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 12 Twp. 30S Rge. 7W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SW NW
Lease Owner National Cooperative Refinery Association
Lease Name Lock-Cessna Unit Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 19, 19 58
Application for plugging filed January 23, 19 58
Application for plugging approved January 23, 19 58
Plugging commenced February 3, 19 58
Plugging completed February 3, 19 58
Reason for abandonment of well or producing formation Unable to complete as a commercial producer.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4525 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253'	None-Cemented
				5 1/2"	4226'	3210-52

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

5-1/2" set at 4226' with 125 sacks of cement. 8-5/8" surface casing set at 253' with 200 sacks of cement. Plugged back total depth 4108'. Top perforations at 4102-4106'. Recovered 3210.52' 5-1/2" casing. Plugged back with sand from 4108-4080'. Dumped 5 sacks of cement. Pulled pipe to 1800', circulated hole through 5-1/2" casing with 70 sacks of Magcogel. Pulled remainder of casing. Set rock bridge at 250'. Mixed and dumped 20 sacks of cement. Mudded hole to 35', set 5' rock bridge. Mixed and dumped 10 sacks of cement on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1958
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ace Pipe Pulling Company
Address Box 304, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of February, 1958

My commission expires November 26, 1960. Nell McComb Notary Public.

PLUGGING
FILE SEC 12 T 30 R 7W
BOOK PAGE 78 LINE 5

LOCK WELL NO. 1

AURORA GASOLINE COMPANY

Total Depth - 4525
Contractor - Rex & Morris Drilling Co.
Commenced - 11-14-57
Completed - 12-3-57

Location - NE SW NW
Section - 12-30S-7W
Kingman County, Kansas

Casing Record:
8 5/8" @ 253 w/ 200 sacks
5 1/2" @ 4245 w/ 125 sacks

FORMATION	DEPTH
Surface Hole	253
Shale & Shells	680
Lime	995
Lime & Shale	1880
Shale & Lime	2690
Lime	2925
Shale & Lime	3115
Lime & Shale	3595
Lime	3835
Lime & Shale	3989
Shale & Lime	4100
Chat	4160
Lime	4340
Lime & Shale	4410
Shale & Lime	4500
Sand T.D.	4525

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

REX & MORRIS DRILLING COMPANY

By Paul D. Hoover
Title Geol.

STATE OF KANSAS)
) SS.
COUNTY OF BUTLER)

Subscribed and sworn to before me, a Notary Public, this 18 day of December, 1957.

Winifred E. Dunt
Notary Public

My Commission expires:

July 23, 1960.

STATE CORPORATION COM.
FEB 20 1960
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 12 T.30 R.70
BOOK PAGE 78 LINE 5