


WELL PLUGGING RECORD

See All Information Completely
See Required Affidavit
File or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 11, Twp 30S, Rge. 7E (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Pickrell Drilling Company
Lease Name Muller Well No. 1
Office Address North Main Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed April 12, 1963 19
Application for plugging approved April 13, 1963 19
Plugging commenced April 20, 1963 19
Plugging completed April 24, 1963 19
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well PB 4152 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	201	none
				5 1/2	none	3544

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved on, cleaned out cellar and worked pipe.

Sanded to 4125' and dumped 5 sx. cement. Worked pipe and shot @ 3800'-3700' - 3600'-3525'. Pulled pipe.

Pulled pipe. Mudded to 215' and built rock bridge. Dumped 6 sx. cement.

Dumped 24 sx. cement and filled hole and rock bridge. Capped well with 10 sx. cement

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1963

COMMISSIONER

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1963

My commission expires July 23, 1966

Carolyn Heren
Notary Public.

15-095-01353-0000 *File Copy*
ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th Natl Bank Bldg
Wichita, Kansas
LOCATION: Muller No. 1 - SW SW NW
11-30S-7W, Kingman County
Kansas

Rotary Drilling Commenced 2-4-63

Rotary Drilling Completed 2-15-63

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD 200' (5 joints) 5/8" Surface Casing set with 160 sacks cement. Circulated.
(135 joints) 5 1/2" Casing set at 4199' with 90 sacks Cement. Completed
at 1:10 P.M. 2-15-63.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

50	Sand	G. F. S.
201	Red Rock	4117
1085	Red Rock-Shale	4132
1600	Lime & Shale	4142
1715	Lime	4152
3367	Lime & Shale	4162
3580	Lime	4200
3290	Lime & Shale	
3862	Lime	
4090	Lime & Shale	Slope Test
4200	Mississippian - TD	1500
		2500
		3500
		4000
		S. L. M.
		2934
		3869
		4171

RECEIVED
STATE CORPORATION

MAY 6 1963

WICHITA, KANSAS

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

On this 22 day of February, 1963, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman Notary Public