

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-095-00169-0001
API NUMBER 8-22-56

LEASE NAME Welch

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 10 TWP. 30S RGE. 7 (E) or (W)

COUNTY Kingman

LEASE OPERATOR Bison Energy Corporation

ADDRESS 9320 E. Central Wichita, Ks. 67206

PHONE# (316) 636-1801 OPERATORS LICENSE NO. 6581

Date Well Completed 8-22-56

Character of Well Oil

Plugging Commenced 5-11-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-16-94

The plugging proposal was approved on April 19, 1994 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Miss Depth to Top 4144 Bottom 4202 T.D. 4202

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-------------|--------------------|----------------|-------------|---------------|-------------|--------------|
| <u>Miss</u> | <u>Oil/Wtr/Gas</u> | <u>surface</u> | <u>200</u> | <u>2 5/8"</u> | <u>200</u> | <u>0</u> |
| | | <u>Surface</u> | <u>4202</u> | <u>5 1/2"</u> | <u>4202</u> | <u>1263.</u> |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

SEE ATTACHED

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. _____

Address Box 333 Attica, Ks. 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bison Energy Corporation


STATE OF Kansas COUNTY OF Sedgwick, ss.

Steven C. Anderson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) 9320 E. Central, Wichita, Ks. 67206

SUBSCRIBED AND SWORN TO before me this 18 day of July, 1994



My Commission Expires: May 13, 1995

Sondra J. Boyd
Notary Public
Sondra J. Boyd

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1994
CONSERVATION DIVISION
Wichita, Kansas

**Welch # 1
Kingman County Kansas**

Plugging Report

5-16-94 SWS ran in hole with the baylor and dumped 5 sx of cement for 2nd plug. Tagged top of 2nd sand plug at 3695'. Rig up ELI to run free point and shoot off pipe. Shot 5 1/2" 14# cgs. off at 1263'. SWS rigged up and pulled 2 jts of 5 1/2" csg. 55.04'. Rig Allied Cement up to pump 35-sx plug at the btm of the salt zone at 1208'. SWS pulled another 16 jts of 5 1/2" csg. 519.08. Rig up Allied Cementing and pumped a 35 sx plug at 689'. Well lost circ. SWS pulled 1 jt of 5 1/2" csg. 33.14. Had tank truck pump 70 bbls of drilling mud and 2 sx of LCM, recovered circ. Allied pumped another 35 sx plug at 656'. Plug held. SWS pulled 12 jts 5 1/2" csg. 383.10. Allied Cementing circ. cement from 273' to surface and rig off well. SWS pulled remaining 5 1/2" csg and rig dwn.

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1994
CONSERVATION DIVISION
Wichita, Kansas