

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman

County. Sec. 10 Twp. 30 Rge. 7 (E) (W)

Location as "NE/CNWKSWK" or footage from lines NW/ NW/ NW

Lease Owner Mull Drilling Company, Inc.

Lease Name H. L. Love Well No. 1

Office Address 670 N. 4th Natl. Bank Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1/29/ 19 59

Application for plugging filed 19 59

Application for plugging approved 2/17 19 59

Plugging commenced 2/17 19 59

Plugging completed 2/24 19 59

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well 4185 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	
				5 1/2	4185	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand to 4088' 5 sacks cement  
Mud to 400' wood plug 10' chat 5 sacks cement  
Mud to 190' wood plug 10' chat 15 sacks cement  
Mud to 30' 10' chat 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Wilson Inc.  
Address Stafford, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
D. G. Comstock (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *D. G. Comstock*  
*Atchison, Kansas*  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of February, 19 59

My commission expires January 28, 1961.  
*Ethel Zimmerman*  
Ethel Zimmerman Notary Public.

PLUGGING  
FILE SEC. 10 T. 30 R. 7W  
BOOK PAGE 15 LINE 21

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al  
Wichita, Kansas

ROTARY DRILLING COMMENCED: 1/5/59

CONTRACTOR: Mull Drilling Co., Inc.  
Wichita, Kansas

ROTARY DRILLING COMPLETED: 1/18/59

CASING RECORD: Set 213' of 8 5/8" cmt/150 sax  
cmt.  
Set 4185' of 5 1/2" cmt/655 sax  
posmix, 35 sax cmt., 35 gal Latex

LOCATION: H. T. Love #1  
NW NW NW 10-30S-7W  
Kingman County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

600'	Red Bed
1300'	Lime & Shale
1765'	Lime
1960'	Lime & Shale
2253'	Shale w/Broken Lime
2938'	Shale & Lime
3339'	Sandy Lime & Shale
3714'	Lime & Shale
3955'	Lime
4045'	Lime & Shale
4185'	Mississippi Lime
	Total Depth

**RECEIVED**  
STATE CORPORATION COMMISSION  
FEB 14 1959  
COMMISSIONER'S OFFICE  
WICHITA, KANSAS


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

*J. A. Mull, Jr.*  
J. A. MULL, JR.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 26th day of January, 1959



*Madge N. Miller*  
Madge N. Miller, Notary Public

Commission Expires: February 24, 1960

PLUGGING			
FILE	SEC	10 T. 30 R. 7W	
BOOK	PAGE	15	LINE 21