

15-095-00082-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kingman

County. Sec. 8 Twp. 30 Rge. 7 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner R. E. Hartman

Lease Name Johnson Well No. 1

Office Address Box 54, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed March 30 19 55

Application for plugging filed March 30 19 55

Application for plugging approved March 30 19 55

Plugging commenced March 30 19 55

Plugging completed March 30 19 55

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well S. S. Greider

Producing formation Depth to top Bottom Total Depth of Well 4235 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		-0-	194	8 5/8"	194	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filed hole with heavy mud to 185'.
Dumped 1/3 sack hulls and plugged.
Cemented with 15 sacks cement.
Filed to 25' with heavy mud.
Dumped 1/3 sack hulls and plugged.
Filed to top with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor A. L. Jackson Drilling Company

Address Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Dick B. Evans, Accountant for (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dick B. Evans

Box 194, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 4th day of April, 19 55.

My commission expires April 27, 1957

23-8390-s 6-51-20M

Notary Public. 4-7-55
PLUGGING DIVISION
FILED SEC 8 Twp 30 Rge 7
BOOK PAGE 107 LINE 36

Well Log
Johnson #1
Kingman County, Kansas

0 - 55	Red Rock
55 - 70	Shale
70 - 194	Blue Shale and Shells
194 - 740	Shale and Shells
740 - 810	Shale
810 - 1050	Blue Shale and Shells
1050 - 1060	Anhydrite, Shells and Shale
1060 - 1080	Shale and Shells
1080 - 1160	Anhydrite, Shells and Shale
1160 - 1180	Anhydrite and Shale
1180 - 1240	Salt and Shale
1240 - 1330	Shale and Shells
1330 - 1720	Shale and Lime
1720 - 1900	Lime and Shale
1900 - 2010	Lime and Shale Breaks
2010 - 2165	Shale and Lime Streaks
2165 - 2350	Shale and Lime
2350 - 2440	Lime and Shale
2440 - 2495	Shale and Lime Streaks
2495 - 2585	Lime and Shale
2585 - 2785	Shale and Lime
2785 - 2965	Lime and Shale
2965 - 3040	Lime
3040 - 3065	Shale
3065 - 3235	Lime and Shale
3235 - 3330	Shale
3330 - 3400	Lime and Shale
3400 - 3735	Lime
3735 - 3785	Lime, Kansas City
3785 - 3841	Lime
3841 - 3970	Lime and Shale
3970 - 4195	Shale and Lime
4195 - 4235	Lime
4235	Misslime T.D.

STATE OF KANSAS
COUNTY OF BARTON ss

Dick B. Evans, Accountant for A. L. Jackson Drilling Company, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Dick B. Evans
Dick B. Evans
Box 194
Great Bend, Kansas

Subscribed and sworn to before me this 4th day of April, 1955.

Walter S. Selford
My Commission Expires April 27, 1957.

PLUGGING
FILE SEC 8 120 R 7W
BOOK PAGE 107 UNK 26