

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-095-20533 8000

LEASE NAME Kohman

RECEIVED

MAY 29 2003
KCC WICHITA

TYPE OR PRINT

NOTICE- Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1980 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 8 TWP. 30 RGE. 7 E W

COUNTY Kingman

Date Well Completed 02-16-77

Plugging Commenced 04-08-03

Plugging Completed 04-08-03

LEASE OPERATOR McCoy Petroleum Corp.

ADDRESS 453 S. Webb Rd., Suite 310, Box 780208 Wichita KS 67278

PHONE # (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04-08-03 (date)

by Doug Louis (KCC District Agent's Name),

Is ACO-I filed? yes If not, Is well log attached? _____

Producing Formation Hertha, Miss Depth to Top 3777 Bottom 4156 T.D. 4545

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	232	none
				4 1/2	4247	2715

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Sand at 3725, bail 4 sacks cement. Shot pipe at 3056, 2715, work free. Pull to 1150, pump 35 sacks cement. Pull to 700, pump 35 sacks cement. Pull to 280, circulate cement to surface with 130 sacks. Pull rest of pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 401 West Main, Lyons KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES McCoy Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick ss.

Scott Hampel (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott Hampel

(Address) 453 S. Webb Rd., Suite 310, Box 780208 Wichita KS 67278

SUBSCRIBED AND SWORN TO before me this 27th day of May, 2003

Dianne Howard
Notary Public

My Commission Expires 03-15-07





INVOICE NO.	Subject to Correction			FIELD ORDER	6207
Date 4-10-03	Lease Kohman	Well # 1	Legal G.305-7W		
Customer ID	County KINGMAN	State KS	Station PRATT		
CHARGE McCoy Petroleum	Depth	Formation	Shoe Joint N/A		
	Casing 4 1/2	Casing Depth 1180'	TD 9173'	Job Type P.T.A. OLD WELL	
	Customer Representative Richard	Treater T-SC30			

AFE Number	PO Number	Materials Received by	X <i>Richard O. McJulie</i>
------------	-----------	-----------------------	-----------------------------

Product Code	QUANTITY	MATERIAL, EQUIPMENT and SERVICES USED	UNIT PRICE	AMOUNT	ACCOUNTING	
					CORRECTION	AMOUNT
D-203	200 sks	60/40 Poz	✓			
C-320	344 lbs	CEMENT Gel	✓			
E-107	200 sks	CEMENT SERV. CHARGE				
E-100	45 mi	UNITS / WAY MILES 45				
E-104	387 TM	TONS MILES				
R-400	1 EA	EA. P.T.A. PUMP CHARGE				
		DISCOUNTED PRICE		2,464.76		
		T TAXES				

TREATMENT REPORT



Customer ID		Date	
Customer Mc Coy P&T		4-10-03	
Lease Kohman		Lease No.	Well # 1
Field Order # 6202	Station PRATT	Casing 4 1/2	Depth 1150'
Type Job P.T.A. OLD WELL		County KINGMAN	State Ks
		Formation	Legal Description 8-30S-7W

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size	Tubing Size	Shots/Ft		Acid 200SKS 60/40 P2		RATE	PRESS	ISIP
Depth	Depth	From	To	Pre Pad 6% Gel		Max		5 Min.
Volume	Volume	From	To	Pad 13.3 gal		Min		10 Min.
Max Press	Max Press	From	To	Frac 1.59 FT³		Avg		15 Min.
Well Connection	Annulus Vol.	From	To			HHP Used		Annulus Pressure
Plug Depth	Packer Depth	From	To	Flush		Gas Volume		Total Load

Customer Representative RICHARD	Station Manager D. AUBRY	Treater T. SEBA
--	---------------------------------	------------------------

Service Units		114	28	44	72				
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log				
07:00					CALL 30 OUT				
08:30					ON LOC W/ TRUCKS & SAFETY MITG.				
					1 ST PLUG @ 1150' 35 SKS 60/40 P2 6% GEL				
9:00			100	3	BREAK CIRC H ₂ O				
			9.91		MIX: PUMP 35 SKS				
			15.5		DISP				
					2 ND PLUG @ 700' 35 SKS 60/40 P2 6% GEL				
			5		BREAK CIRC H ₂ O				
			9.91		MIX: PUMP 35 SKS				
			8.3		DISP				
					3 RD 200'				
			2	3	BREAK CIRC H ₂ O				
					MIX: PUMP 130 SKS				
			36.8		CIRC OUT TO SURFACE				
10:00					JOB COMPLETE				
					THANKS				
					T200				

10244 NE Hiway 61 • P.O. Box 8613 • Pratt, KS 67124-8613 • Phone (620) 672-1201 • Fax (620) 672-5383