

15-119-00038-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Meade County, Sec. 10 Twp. 31S Rge. 30W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NW

Lease Owner Aladdin Petroleum Corporation

Lease Name Gano Well No. 1

Office Address 809 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 11 19 56

Application for plugging filed May 11 19 56

Application for plugging approved May 11 19 56

Plugging commenced May 11 19 56

Plugging completed May 11 19 56

Reason for abandonment of well or producing formation No oil in commercial quantities found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 5582 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1407'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 500'. Set #1 plug with 35 sacks cement. Filled hole with extra heavy rotary mud to 40'. Set #2 plug with 15 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.

Address 1005 Central Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss. L. J. Clampitt (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] 1005 Central Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 19 56

My commission expires Sept. 30, 1959

Darlene May Notary Public.

RECEIVED STATE CORPORATION COMMISSION MAY 16 1956 CONSERVATION DIVISION Wichita, Kansas

PLUGGING FILE SEC 10 T 31 R 30W BOOK PAGE 61 LINE 6

ROTARY DRILLING LOG

OPERATOR: Aladdin Petroleum Corporation
 Gano #1
 C NW NW Sec. 10-31S-30W,
 Meade County, Kansas

CONTRACTOR: Capitt Drilling, Inc!
 COMM: 4/15/56
 COMP: 5/11/56

Remarks: Set 8-5/8" casing at 1407'
 cemented with 400 sacks Pozmix cement,
 2% C. C. on bottom, 500 sacks Pozmix,
 2% C. C. through D.V. tool at 781'

15-119-60386-0000

Formations:

Cellar	10'
Shale	95'
Sand & Salt	376'
Sand	470'
Red Rock - Sand	800'
Red Rock	970'
Lime	1085'
Shale	1105'
Shale - Lime	1344'
Shale	1372'
Lime	1445'
Red Bed - Shells	2130'
Shale Lime Anhydrite	2340'
Anhydrite & Shale	2500'
Shale, Anhydrite & Lime	2655'
Lime & Shale	3093'
Lime	3428'
Lime Shale	3493'
Lime	3570'
Lime Shale	3830'
Lime	3880'
Lime & Shale	4018'
Lime	4155'
Lime & Shale	4255'
Lime	4295'
Lime & Shale	4375'
Lime	4813'
Lime & Shale	4924'
Lime	4945'
Shale & Lime	5161'
Lime	5353'
Lime Shale Bks.	5396'
Lime	5463'
Lime & Shale	5582'
Rotary Total Depth (D&A)	5582'

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

CAPITT DRILLING, INC.

R. R. McNicol

R. R. McNicol

RECEIVED
 APR 16 1956

PLUGGING
 FILE SEC. 10 T. 31 R. 30W
 BOOK PAGE 61 LINE 6