

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20,743-0000

LEASE NAME Borth

WELL NUMBER 24-12

660 Ft. from S Section Line

3315 Ft. from E Section Line

SEC. 12 TWP. 31 RGE. 30 (X) or (W)

COUNTY Meade

Date Well Completed 07-24-86

Plugging Commenced 04-27-93

Plugging Completed 05-06-93

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Giant Exploration & Production

ADDRESS P.O. Box 2810

PHONE# (505) 326-3325 OPERATORS LICENSE NO. 9534

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04-28-93 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Chester Depth to Top 5454' Bottom 5512' T.D. 5590'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chester	Gas	5454	5464	8-5/8	1645'	0
Chester	Gas	5504	5512	5-1/2	5585'	2547'
				2-3/8	5504'	5504'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pump 25 sks of hulls and 25 sks of cement to 5350'

Pump 25 sks of cement from 3370' to 3100'

Pump 50 sks of cement from 1700' to 1600'. Pump 40 sks of cement from 700' to 600'

Put 10 sks of cement from 40' to surface, cut off and cap 8-5/8" casing 4' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506, Liberal, KS 67405-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Giant Exploration & Production Company

STATE OF New Mexico COUNTY OF San Juan, ss.

John C. Corbett (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John C. Corbett

(Address) P.O. Box 2810, Farmington, NM 87499

SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 93

Virginia Lawrence
Notary Public

My Commission Expires: 04/29/97

RECEIVED
JUN 21 1993
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

