

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

3-12  
API NUMBER 15-025-20,827-0007

LEASE NAME Shrauner

WELL NUMBER 1-4

SPOT LOCATION 137' S of NW

SEC. 4 TWP. 31S RGE. 21W (E) or (W)

COUNTY Clark

Date Well Completed \_\_\_\_\_

Plugging Commenced 1-10-85

Plugging Completed 3-12-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kelso Casing Pulling - Purchased From

ADDRESS Box 347 Chase, Ks. 67524 Quintana Petroleum Corp.

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well OIL  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 5236'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	700'	none
				5-1/2"	5235'	4001'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 5135' and 5 sacks cement. Shot casing @4421', 4226', 4001' and pulled a total of 96 joints of 5-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, released plug and displaced with 150 cement, 60/40 pos, 2% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347 Chase, Kansas 67524

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

MAR 15 1985

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 13th day of March, 1985



Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_