

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-21,208 0000

LEASE NAME Shrauner "M"

WELL NUMBER 1

690 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 6 TWP. 31 RGE. 21W (E) or (W)

COUNTY Clark

Date Well Completed

Plugging Commenced 2-4-03

Plugging Completed 2-6-03

RECEIVED

FEB 12 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Robinson Energy & Exploration, Inc.

ADDRESS 300 W. Douglas, Suite 420 Wichita, Kansas 67202

PHONE (316) 262-6734 OPERATORS LICENSE NO. 5038

Character of Well Gas

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	692'	None
				4-1/2"	5304'	3500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from _____ feet to _____ feet each s. Set CIBP @5100 and dumped 2 sacks cement on top. Shot casing loose @3500', pulled up to 1330', pumped 10 sacks gel and 50 sacks cement, pulled up to 710', pumped 50 sacks cement, pulled up to 312', pumped 25 sacks cement, circulated 10 sacks cement @40'. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robinson Energy & Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 11th day of February, 2003

Irene Herzberg
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 2-24-05

Form 9
Revised 05-