

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-025-204/S 2000

Give All Information Completely
 Make Required Affidavit

COUNTY Clark SEC. 7 TWP. 31s RGE. 21w E/W
 Location as in quarters or footage from lines:
150' S of S $\frac{1}{2}$ N $\frac{1}{2}$

Lease Owner Imperial Oil Co.
 Lease Name Daily # 1-7 Well No. _____
 Office Address 720 Fourth Financial Center, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 2/23/83
 Plugging completed 2/28/83
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom T.D. 5238'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	628'	none
				4 1/2"	5237'	4000'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged off bottom with sand to 5050' & ran 4 sacks cement, Shot pipe at
 4000' Pulled total of 95 joints. Squeezed hole with 3 sacks hulls, 25
 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug &
 displaced with 150 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
 Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 83

My Commission expires:



RECEIVED
 STATE CORPORATION COMMISSION
 Notary Public.

MAR 7 1983

CONSERVATION DIVISION
 Wichita, Kansas