

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

CLARK County. Sec. 14 Twp. 31S Rge. (E) 21 (W)

Location as "NE/CNWxSWx" or footage from lines NE NE NW

Lease Owner FALCON SEABOARD DRILLING COMPANY

Lease Name BERRYMAN Well No. 1

Office Address STANOLIND

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed OCTOBER 10, 19 55

Application for plugging filed OCTOBER 11, 19 55

Application for plugging approved OCTOBER 12, 19 55

Plugging commenced OCTOBER 11, 19 55

Plugging completed OCTOBER 11, 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. A. RIVES

Producing formation Depth to top Bottom Total Depth of Well 5300 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				20"	90	None
				13 3/8"	537	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

HOLE WAS FULL OF MUD. SET 13" PLUG AT 525' AND RAN 30 SACKS OF CEMENT ON TOP OF PLUG. SET 2ND PLUG AT 25' AND FILLED TO TOP OF SURFACE CASING WITH 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor FALCON SEABOARD DRILLING COMPANY

Address STANOLIND BUILDING, TULSA, OKLAHOMA

STATE OF OKLAHOMA, COUNTY OF TULSA, ss. I. O. BROWN

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. O. Brown

Stanolind Bldg. Tulsa, Okla (Address)

SUBSCRIBED AND SWORN to before me this 18TH day of OCTOBER, 19 55

Dolores Walsh

My commission expires Feb. 8, 1955

RECEIVED Notary Public.
STATE CORPORATION COMMISSION
OCT 18 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 14 T 31 S 21 W
BOOK PAGE 8 LINE 8

WELL LOG

COMPANY - Falcon Seaboard Drilling Company

Sec. 14-31S-21W

FARM - Berryman No. 1

Loc. NE NE NW

County - Clark

TOTAL DEPTH - 5300'

15-025-00018-0000

COMM. 9- 7-55 COMP. - 10-10-55

CONTRACTOR - Company Tools.

ELEVATION

CASING

D.F. - 2183

20" - 90'

Gr. - 2176

13 3/8" - 537'

DRILLER'S LOG

Sand, Clay & Shale	0	90
Shale	90	190
Shale, Shells & Red Bed	190	540
Shale & Shells	540	1060
Red Bed	1060	1239
Shale & Shells	1239	2308
Shale & Lime	2308	3085
Lime	3085	3156
Lime & Shale	3156	3294
Lime	3294	3411
Lime & Shale	3411	3435
Lime	3435	3981
Lime & Shale	3981	4630
Lime	4630	5077
Lime & Shale	5077	5212
Lime	5212	5300

TOTAL DEPTH 5300

PLUGGING
 SEC. 14-31 R21W
 BOOK PAGE 8 LINE 8

ED
 COMMISSION
 027 1955
 CONSERVATION DIVISION
 Wichita, Kansas