

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,477-0000

LEASE NAME Farmer

WELL NUMBER 1

SPOT LOCATION 100'W/C W/2 SE

SEC. 17 TWP. 28 RGE. 12 or (W)

COUNTY Pratt

Date Well Completed 10-9-84

Plugging Commenced 10-9-84

Plugging Completed 10-9-84

LEASE OPERATOR J.A. ALLISON  
ADDRESS 300 W. Douglas Suite 305 Wichita, Ks. 67202

PHONE # (316) 263-2241 OPERATORS LICENSE NO. 5027

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 2950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged well with 140 sxs 60/40 poz, 2% gel, 3% cc as follows: 630' - 60 sxs; 240' - 50 sxs; 40' - 10 sxs; rathole - 15 sxs; water well - 5 sxs. Job by Allied. Plug down at 9:30 pm on October 9, 1984.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149  
Address P.O. Box 329 Pratt, Kansas 67124


RECEIVED

STATE OF KANSAS COUNTY OF PRATT, ss. STATE CORPORATION COMMISSION

Tracy C. Graven (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tracy C. Graven

(Address) P.O. Box 329 Pratt, Ks. 67124




SUBSCRIBED AND SWORN TO before me this 18 day of October, 1984

Mary L Tjaden  
Notary Public

My Commission expires: 3/22/88

# Wheatstate



## Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

### DRILLERS' WELL LOG

Farmer #1  
 100' W/C W/2 SE Sec. 17-28-12W  
 Pratt County, Kansas  
 Commenced: 10-4-84  
 Completed: 10-9-84  
 API #15-151-21,477  
 Operator : J.A. Allison

From	DEPTH To	FORMATION	REMARKS
0	580'	Sand, Shale	Ran 6 joints (202'), new 60#, 13 3/8" surface casing. Set at 206' with 175 sxs 60/40 poz, 2% gel, 3% cc. Job by Allied.
580'	996'	Clay, Sand	
996'	1707'	Sand, Shale	Plug down at 5:45 pm on October 4, 1984.
1707'	1737'	Shale	
1737'	2047'	Shale, Clay, Lime	RTD 2950'  Plugged well with 140 sxs 60/40 poz, 2% gel, 3% cc as follows: 630' - 60 sxs; 240' - 50 sxs; 40' - 10 sxs; rathole - 15 sxs; water well - 5sxs. Job by Allied. Plug down at 9:30 pm October 9, 1984. State Plugger was out of the Dodge City, Kansas office.
2047'	2363'	Sand, Shale, Lime	
2363'	2950'	Shale, Lime, T.D.	

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RECEIVED  
 STATE CORPORATION COMMISSION

WHEATSTATE OILFIELD SERVICES, INC. OCT 22 1984



*Arnie Little*  
 Arnie Little, Vice-President

CONSERVATION DIVISION  
 Wichita, Kansas

*Mary L. Tjaden*  
 Notary Public, Mary L. Tjaden

My Commission Expires:

*3/22/88*