

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,540 ^{00.00}

LEASE NAME C. Banbury

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 17 TWP. 28 RGE. 12 (N) or (W)

COUNTY Pratt

Date Well Completed 1-13-85

Plugging Commenced 1-14-85

Plugging Completed 1-14-85

LEASE OPERATOR J. A. Allison

ADDRESS 300 W. Douglas, Suite 305, Wichita, Kansas 67202

PHONE#(316) 263-2241 OPERATORS LICENSE NO. 5027

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 2970

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 125 sxs 50/50 poz, 4% gel as follows: 700'-50 sxs; 250'-50 sxs; 40'-10 sxs with solid bridge; rathole-10 sxs; water well-5 sxs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

James A. Easter (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James A. Easter

(Address) P. O. Box 329, Pratt, Kansas 67124




SUBSCRIBED AND SWORN TO before me this 17th day of January, 1985

Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1985
01-22-85



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

C. Banbury #1
 C SW SW Sec. 17-28S-12W
 Pratt County, Kansas
 Commenced: 1-7-85
 Completed: 1-14-85
 API #15-151-21,540
 Operator: J. A. Allison

Depth		Formation	Remarks
From	To		
0	212	Surface Sand	Ran 5 joints (200') new, 13 3/8" surface casing. Set at 204' with 175 sxs 60/40 poz, 2% gel, 3% cc. Job by Allied. Plug down at 1 a.m. on January 8, 1985.
212	1130	Sand, Clay	
1130	1244	Shale, Lime	
1244	1400	Sand, Clay	
1400	2290	Shale	
2290	2970	Shale, Lime T.D.	
			RTD 2970'
			Plugged well with 125 sxs 50/50 poz, 4% gel as follows: 700'-50 sxs; 250'-50 sxs; 40'-10 sxs with solid bridge; rathole-10 sxs; water well-5 sxs. Job by Allied. Plug down at 2:40 p.m. on January 14, 1985. State Plugger was Paul Lucas out of the Dodge City, Kansas office.

STATE OF KANSAS)
)
 COUNTY OF PRATT) ss

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.



James A. Easter
 JAMES A. EASTER, OPERATIONS COORDINATOR

Mary L. Tjaden
 NOTARY PUBLIC

My Commission Expires:

3/22/88

RECEIVED
 STATE CORPORATION COMMISSION

JAN 22 1985

CONSERVATION DIVISION
 Wichita, Kansas