

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-129-20,793-100 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE (316) 624-6253

LEASE JOHNS "B" WELL# 1 SEC. 26 T. 31S R. 41 (XXXX/West)

- C - SE - SW SPOT LOCATION/QQQQ COUNTY MORTON

660 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

3300 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1520' CEMENTED WITH 700 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 5352' CEMENTED WITH 215 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: CIBPS: 3235' & 4157' PERFS: 2176-2199'

ELEVATION 3360' / -- T.D. 5600' PBDT 5350' ANHYDRITE DEPTH 1510'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU WL. RIH AND SET CIBP @ 2150'. DMP 2 SKS CLASS "H" CMT ON TOP OF CIBP. RDMO WL. MIRU CSG PULLERS. PULL ON 4-1/2" CSG & LOCATE FREE POINT. SHOOT OFF 4-1/2" CSG. TOH W/1 JT OF 4-1/2" CSG & CIRC HOLE W/9 PPG MUD. TOH W/4-1/2" CSG TO 1620'. SPOT 75 SXS CLASS "H" PREMIUM CMT FROM 1620-1420' (100' ABOVE & BELOW SURFACE CSG). TOH W/4-1/2" TO 54'. SPOT 17 SXS CLASS "H" PREMIUM CMT FROM 54-4'. TOH W/REMAINING 4-1/2" CSG. CUT OFF 8-5/8" CSG 4' BELOW GL & CAP. INSCRIBE CAP W/WELL NAME & NUMBER. LEGAL DESCRIPTION, & PLUGGING DATE. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS

MR. TERRY LEWIS PHONE# (316) 697-2188

ADDRESS P.O. DRAWER X City/State ELKHART, KANSAS 67950

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 9215
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/5/97 AUTHORIZED OPERATOR/AGENT: John A. Broman

JOHN A. BROMAN (Signature) DIV. PROD. ENGR.

RECEIVED
KANSAS STATE CORPORATION COMMISSION
1997 MAR 18 P 1:38



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

March 7, 1997

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Johns "B" #1
API 15-129-20,793-6000
660 FSL 3300 FEL
Sec. 26-31S-41W
Morton County

Dear Mr. Terry Lewis,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760