

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 025-20443-00-01 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR American Exploration Company OPERATOR'S LICENSE NO. 04680
77002

ADDRESS 2100 RepublicBank Center, Houston, Tex. PHONE # (713) 237-0800

LEASE (FARM) Giles, Norman A WELL NO. 2-24 WELL LOCATION NE/4 SE/4 COUNTY Clark

SEC. 24 TWP. 31S RGE. 22W (E) or (W) TOTAL DEPTH 5270' PLUG BACK TD 3700'

Check One:

OIL WELL ☒ GAS WELL ☐ D & A ☐ SWD or INJ WELL ☐ DOCKET NO. 250 sx. Lt. Wt.

SURFACE CASING SIZE 8-5/8 SET AT 672 CEMENTED WITH +150 sx. "A" SACKS

CASING SIZE 4-1/2 SET AT 5245 CEMENTED WITH 200 sx. 50/50 ^{poz} SACKS

PERFORATED AT 5104-16' (Miss. Lime) 3566-78 (Wolfcamp) 3413-3424 (Wolfcamp)

CONDITION OF WELL: GOOD ☒ POOR ☐ CASING LEAK ☐ JUNK IN HOLE ☐

PROPOSED METHOD OF PLUGGING Circ. hole w/9.5 ppg. mud. Set CIBP @ 3550', dump 2 sx.

cmt. on top. GIH w/tbg. and spot 200 cmt. plug from 772-572'. Spot 20' cmt. plug

from 30-10'. Cut off csq. 4' below ground level.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? ☐ IS ACO-1 FILED? No
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Oct., 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Frank Pardee PHONE # (405) 752-9036

ADDRESS 2932 N.W. 122nd., Suite 23, Oklahoma City, Oklahoma 73120

PLUGGING CONTRACTOR American Exploration Company LICENSE NO. 04680
77002

ADDRESS 2100 RepublicBank Center, Houston, Tex. PHONE # (713) 237-0800

PAYMENT OF THE PLUGGING FEE RECEIVED 82-3-118 WILL BE GUARANTEED BY OPERATOR OR AGENT.

STATE CORPORATION COMMISSION

SIGNED:

OCT 26 1989

W. B. McQuinn
(Operator or Agent)

CONSERVATION DIVISION DATE:
Wichita, Kansas

Oct. 24, 1989

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE

JAN 26 1990

EXPIRES

October 26, 1989

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

American Exploration Company
2100 RepublicBank Center
Houston, TX 77002

15-025-20443-00-01
Giles, Norman A. 2-24
NE/4 SE/4
Sec. 24-31-22W
Clark County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor

Dodge City, KS. 67801

(316) 225-6760