


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 23 Twp. 28 Rge. 12 (E) (W)
CW/2 NE NW

Location as "NE/CNW/SW" or footage from lines
Raymond Oil Co., Inc.

Lease Owner _____

Lease Name Chitwood #12 Well No. _____

Office Address Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19 _____

Application for plugging filed _____ 19 _____

Application for plugging approved _____ 19 _____

Plugging commenced 11/24/70 _____ 19 _____

Plugging completed 11/28/70 _____ 19 _____

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4476 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	340	none
				5 1/2"	4471	1595'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Raised mast, bled gas from well, called water truck out and pumped two loads water. Ran sand to 1860' and dumped 5 sacks of cement. Shot pipe at 1700 and 1606', pipe came loose, pulled 52 joints. Bailed fluid down to 275' and set rock bridge, dumped 4 1/2 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 - 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 70

Margaret Melsker
Notary Public.

My commission expires 2/15/71


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

COPY

Company - LION OIL COMPANY
Farm - Chitwood No. 12

SEC. 25 T. 28 R. 12 W
CW 1/2 NE NW

Total Depth. 4476'
Comm. 10-24-45 Comp. 11-19-45
Shot or Treated. 1000 acid
Contractor. R. W. King Drig. Co.
Issued. 1-5-46



CASING:
8 5/8" 340'
5 1/8" 4471'

Elevation. _____

Production. Swab 9 BOFH

Figures Indicate Bottom of Formations.

clay	0-290
red bed	340
shale & red bed	575
shale & shells	1325
shale	1625
shale & lime	1785
lime	2375
shale	2702
lime & shale	2880
lime	2963
lime & shale	3259
lime	3276
lime & shale	3744
lime	4125
shale & lime	4472
lime	4476
Total Depth.	

Tops:
Lansing 3703
Viola 4268
Simpson shale 4362
Simpson sand 4368
Arbuckle 4470

Acidized w/1000 gals:

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1970
CONSERVATION DIVISION
Wichita, Kansas