


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 23 Twp. 28S Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines 969.8' E & 394' S NWcNW/4

Lease Owner Raymond Oil Co., Inc. Well No. WS-1 (15)

Lease Name Chitwood

Office Address Wichita, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed Dec. 5 19 45

Application for plugging filed Dec. 17 19 69

Application for plugging approved Dec. 17 19 69

Plugging commenced Feb. 6 19 70

Plugging completed Mar. 4 19 70

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Biberstein

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Includes a 'RECEIVED' stamp from the State Corporation Commission dated MAR 24 1970.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3690' and dumped 7 sacks of cement. Shot pipe off at 1542.12'. Pulled pipe and mudded hole to 275'. Set 10' rock bridge and dumped 35 sacks of cement. Mudded to 40'. Set 10' rock bridge and dumped 15 sacks of cement at base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.

STATE OF Kansas, COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self

R. R. #4, Hutchinson, Kans. 67501 (Address)

SUBSCRIBED AND SWORN to before me this 18th day of March, 19 70

October 18, 1973



Dorothy Self (Signature)

Notary Public.

WELL LOG

CHITWOOD #15

Location: 969.8' East and 394.0' South of NW Cor. NW⁴Sec. 23-28-12W
Pratt County, Kansas.

Operator: Lion Oil Company
Contractor: Holm Drilling Company
Total Depth: 3744'
Casing:
10"-15 Jts-320'-Cemented 200 sx
7"-11' Jts-3700'-Cemented 200 sx

Commenced: 10-31-45
Spudded: 10-31-45
Prod. String Set: 11-16-45
Rotary Moved Out: 11-17-45
Cable Moved In: 11-18-45
Completed: 12- 5-45

FORMATION


DEPTH

Clay	40	
Gravel and Shale, Red	265	
Shale, Red	830	
Shale	880	
Shale and Lime Shells	1225	
Salt and Shale	1275	
Shale and Lime Shells	1365	
Shale and Lime	1540	
Shale and Shells	1645	
Lime, Gray	1700	
Lime, Gray, Hard	1742	
Lime and Gyp	1765	
Lime and Shale	1960	
Lime and Gyp	2000	
Lime	2045	
Lime and Shale	2140	
Lime, Broken	2225	
Lime, Gray, Hard	2275	
Lime and Shale	2825	
Lime, Gray	2880	
Lime, Gray, Hard	2925	
Lime and Shale	3000	
Lime, Gray	3170	
Lime, Broken	3400	
Lime, Light, Hard	3440	
Lime and Shale	3475	
Lime, Dark, Hard	3515	
Lime, Broken	3555	
Shale, Gray	3565	
Lime and Shale	3700	Total Rotary Depth
Shale	3725	
Lime, K. C.	3744	T. D.

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of Well Log of the Chitwood #15 Well located 969.8' East and 394' south of NW Cor. NW⁴Sec. 23-28S-12W Pratt County, Kansas.

By



J. C. HATFIELD
HOLM DRILLING COMPANY