

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-20280-00-00

LEASE NAME Chitwood

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER S-1

3630 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 23 TWP. 28 RGE. 12 CE or (W)

COUNTY Pratt County

LEASE OPERATOR Raymond Oil Company, Inc.

ADDRESS P.O. Box 48788, Wichita, KS 67201

PHONE# (316) 267-4214 OPERATORS LICENSE NO. 5046

Date Well Completed 5-2-75

Character of Well Gas

Plugging Commenced 3-16-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-16-94

The plugging proposal was approved on 3-16-1994 (date)

by Mr. Steve Pfiefer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Indian Cave Depth to Top 2646 Bottom 2670 T.D. 3171

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-------------|-----------|------|-------|-------|--------|------------|
| Surface | Sand/Clay | 325 | Surf. | 8 5/8 | 325' | None |
| Indian Cave | Sand/Lime | 325 | RTD | 4 1/2 | 2850' | None |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
4 1/2" 25 Sacks cement from 2500' to 2200'. 11 Sacks from 2200' to 700' 60 Sacks cement from 700 to surf. 8 5/8" 115sx cmt from 325 to surface. All cement was 60-40 poz-mix 6% Gel. State plugger was Steve Pfiefer.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor United Cementing Co. License No. _____

Address 2510 W. 16th, El Dorado, KS 67042

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Raymond Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

William S. Raymond

(Employee of Operator) of Operator _____

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 48788, Wichita, KS 67201

AND SWORN TO before me this 17th day of March, 19 94



[Signature]
 Notary Public Kellie S. Carter

My Commission Expires: June 15, 1997

03-18-94
 RECEIVED
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas