

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR MESA OPERATING LIMITED PARTNERSHIP

ADDRESS P.O. BOX 2009, AMARILLO, TEXAS 79189

PHONE# (806) 378-1000 OPERATORS LICENSE NO. #04824

Character of Well P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation Council Grove Depth to Top 2465 Bottom 3075 T.D. 5330'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Council Grove	salt water	2465	3075	8 5/8"	674'	none
				4 1/2"	5329'	1420'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

MIRU Pool Rig, loaded hole with 9.2 ppg mud, shot 4 1/2" @ 1420', POH to 1380', circ hole w/9.2 ppg mud; mix & spot 30 sx Class "H" plug 1380' - 1300'; POH to 710'; mix & spot 50 sx Class "H" 710'-610', POH to 30', mix & spot 10 sx Class "H" 30'-10'. cut wellhead 3' BGL
 (If additional description is necessary, use BACK of this form.) Weld on cap, Well P&A

Name of Plugging Contractor Pool Well Servicing Company License No. 7874

Address P.O. Box 998, El Reno, Oklahoma 73036

STATE OF TEXAS COUNTY OF POTTER, ss.

Carolyn L. Cummings

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn Cummings

(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 8th day of June, 19 87

My Commission Expires: 8-6-89 Notary Public STATE CORPORATION COMMISSION

JUN 11 1987

Form CP-4
 Revised 08-84