

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20,312-0000

LEASE NAME SEACAT

WELL NUMBER # 8-19

4620' Ft. from S Section Line

2820' Ft. from E Section Line

SEC. 19 TWP. 31S RGE. 21 (E) or (W)

COUNTY Clark

Date Well Completed 11-8-79

Plugging Commenced 6-2-87

Plugging Completed 6-3-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR MESA OPERATING LIMITED PARTNERSHIP

ADDRESS P.O. BOX 2009, AMARILLO, TEXAS 79189

PHONE (806) 378-1000 OPERATORS LICENSE NO. #04824

Character of Well P&A

(Oil), Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes if not, is well log attached?

Producing Formation Mississippi Depth to Top 5057' Bottom 5182' T.D. 5350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	oil	5110'	5182'	8 5/8"	634'	none
				4 1/2"	5323'	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 5050' w/2 sx cement on top; filled hole w/9.2 ppg mud; cut 4 1/2" casing @ 2700'; POH w/1 jt., circ hole w/9.2 mud; set 50 sx Class "H" cement plug from 2360' - 2260'; POH w/casing to 680'; set 50 sx Class "H" cement plug from 680' - 580'; POH to 33'; set 10 sx plug from 33'-3'; cut wellhead 3' BGL; Well P&A

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pool Well Servicing Co. License No. 7874

Address P.O. Box 998, El Reno, Oklahoma 73036

STATE OF TEXAS COUNTY OF POTTER, ss.

Carolyn L. Cummings (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn Cummings

(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 5th day of NOVEMBER, 1987

RECEIVED
STATE CORPORATION COMMISSION
[Signature]
Notary Public

My Commission Expires: 8-6-89

CONSERVATION DIVISION
Wichita, Kansas