

API NUMBER 15-025-20,509-0000

LEASE NAME SEACAT

WELL NUMBER 9-19

2400 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 19 TWP. 31S RGE. 21 (E) or (W)

COUNTY Clark

Date Well Completed 4/27/82

Plugging Commenced 6/3/87

Plugging Completed 6/4/87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR MESA OPERATING LIMITED PARTNERSHIP

ADDRESS P.O. BOX 2009, AMARILLO, TEXAS 79189

PHONE# (806) 378-1000 OPERATORS LICENSE NO. # 04824

Character of Well P&A

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 5109 Bottom 5124 T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	oil	5109	5124	8 5/8"	667'	none
				4 1/2"	5277'	2725'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP set @ 5000' with 2 sx on top; filled hole w/9.2 ppg mud; shot 4 1/2" csg @ 2725';  
 POH w/2 its csg to 2650', set 50 sx Class "H" plug from 2650-2550'; POH to 720', set 50 sx  
 Class "H" plug from 720'-620'; POH to 30', set 10 sx Class "H" from 30'-10'; cut off wellhead  
 3' BGL; well P&A 6/4/87

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pool Well Servicing Co. License No. 7874

Address P.O. Box 998, El Reno, Oklahoma 73036

STATE OF Texas COUNTY OF Potter, ss.

Carolyn L. Cummings (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn Cummings

(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 5th day of June, 1987

RECEIVED  
 STATE CORPORATION COMMISSION  
Shirley D. [Signature]  
 Notary Public

My Commission Expires: 8-6-89

CONSERVATION DIVISION  
 Wichita, Kansas