

STATE OF KANSAS.  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-025-20690-0000

LEASE NAME SEACAT SWS

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

3930 Ft. from S Section Line

350 Ft. from E Section Line

SEC. 19 TWP. 31S RGE. 21 (E) or  (W)

COUNTY Clark

LEASE OPERATOR Mesa Operating Limited Partnership

ADDRESS P.O. Box 2009, Amarillo, Texas 79189

PHONE# (806) 378-1000 OPERATORS LICENSE NO. #04824

Date Well Completed 4/18/84

Character of Well P&A

Plugging Commenced 6/11/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/11/87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Cedar Hills Depth to Top 384' Bottom 389' T.D. 407'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cedar Hills	salt water	384'	89'	7"	384'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

MIRU Pool Well Service, TIH on annulus of 7" w/1" tbg to ±40'; tag solid; RU BJ and circ w/water, mix & pump 40 sx Class "H" cement, circ to surface, TIH w/2 7/8" tbg inside 7" casing; tag @ ±380'; mix & pump ±200 sx Cl "H", circ cement to surf; fell back to ±70'; fill hole w/ ±5 sx Cl H, fell back to 20'; cut off csg head, dump 2 sx cmt in 7", weld on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pool Well Service Co. License No. 7874

Address P.O. Box 998, El Reno, Oklahoma 73036

STATE OF TEXAS COUNTY OF POTTER, ss.

Carolyn L. Cummings (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn Cummings

(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 15th day of June, 19 87

[Signature]  
Notary Public

My Commission Expires: 8-6-89

JUN 17 1987

xc: KCC (orig +1), Prod Rcds, Reg, Expl., CR, Land, Acctg, Partners

Form CP-4  
CONSERVATION DIVISION  
Wichita, Kansas  
Revised 08-84