

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION Form CP-4  
Rev. 12-15-80

DEC 27 1983

CONSERVATION DIVISION  
Wichita, Kansas

15-025-20710-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Clark SEC. 19 TWP. 31 RGE. 21 NE/W  
Location as in quarters or footage from lines:  
2640' FNL & 350' FEL


Lease Owner Mesa Petroleum Co.  
Lease Name Seacat SWS Well No. 2  
Office Address P. O. Box 2009 / Amarillo, TX 79189  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed N/A  
Application for plugging filed 10-24-83  
Plugging commenced 12-20-83  
Plugging completed 12-20-83  
Reason for abandonment of well or producing formation insufficient salt water entry

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi  
Producing formation N/A Depth to top \_\_\_\_\_ bottom T.D. 565'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Sandstone	Salt Water (120,000 mg/L Cl)	358'	368'	7" (7" screen)	355' 562' to 355'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Dumped 3 1/2 yds gravel from 520' to 290'. Set 30 sx Class "A" cement from 290' to 215'. Dumped 4 yds gravel from 215' to 50'. Set 13 sx "A" from 50' to surface. Cut off 7" csg 3' below ground and welded on dry hole cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mesa Petroleum Co. (5575)

STATE OF Texas COUNTY OF Potter, ss.  
R. E. Mathis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Mathis  
P. O. Box 2009/Amarillo, TX 79189  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 1983

My Commission expires: 8/22/87

XC: KCC (O+1), CEN RCDS, ACCTG, MAT CONT, RES ENG, OPS(FILE), MID CONT, PARTNERS

