

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-625-20736-0000

Give All Information Completely
 Make Required Affidavit

COUNTY Clark SEC. 19 TWP. 31 RGE. 21 E/W
 Location as in quarters or footage from lines:
2168' FNL & 970' FEL

Locate Well
 correctly on above
 Section Platt.

Lease Owner Mesa Petroleum Co.
 Lease Name Seacat SWS Well No. 3
 Office Address P. O. Box 2009 / Amarillo, Texas 79189
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed N/A
 Application for plugging filed 11-1-83
 Plugging commenced 12-20-83
 Plugging completed 12-20-83
 Reason for abandonment of well or producing formation Insufficient salt water

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
 Producing formation N/A Depth to top bottom T.D. 446'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Sandstone	Dry	0	446	8 5/8"	363	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 446 feet to Surface feet for each plug set. Dumped 3 yds gravel from 424' to 370'. Set 30 sx Class "A" from 370' to 295'. Dumped 4 yds gravel from 295' to 50'. Set 20 sx "A" from 50' to surface. Cut off 8 5/8" csg 3' below ground and welded on dry hole cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mesa Petroleum Co.

STATE OF TEXAS COUNTY OF POTTER, ss.
R. E. Mathis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Mathis
P.O. Box 2009 / Amarillo, TX 79189
 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 1983

Laura Fox
 Notary Public
 STATE CORPORATION COMMISSION
 RECEIVED
 DEC 27 1983

My Commission expires: 8/22/87

XC: KCC (0+1), CEN RCDS, ACCTG, MAT CONT, RES ENG, OPS(FILE), MID CONT, PARTNERS

CONSERVATION DIVISION
 Wichita, Kansas